


WALL PROTECTIONS AND HANDRAILS

spm-international.com



2021/2022 COLLECTION

CONTENTS

INTRODUCTION 4/15

- About us 4/5
- 100% HEALTH 6/7
- Hygiene is a priority 8/9
- Resistance and protection 10/11
- A range that respects the environment 12/13
- SPM continues to innovate for you 14/15

SELECTION GUIDE: specific solution per sector 16/37

- Specific solutions per sector 16/17
- Hospitals - Clinics 18/21
- Retirement homes - Disability Centers 22/25
- Education 26/29
- Offices - Hotels - Catering - Housing 30/33
- Industry - Sport 34/37

COLOUR RANGE 38/47

- A palette of 33 colours 38/39
- Decowood range 40/41
- Decotrend range 42
- Decosmic panels 43
- Early Childhood 44
- Safy range "individual protection" 45
- A practical guide 46/47

WALL PROTECTION48/87

SPM has developed a range of three products that have been tested: wall protection rails, protection plates and the protection and covering panels.

CORNER PROTECTION 88/101

Our corner protectors are adhesived or with aluminium core and can be applied to all corners, whether right angled or not. All have the same properties: they resist impact and effects of cleaning products.

DOOR PROTECTION102/113

SPM has developed a range of plates and panels to suit all types of door. The panels come in a variety of original and decorative shapes and can be folded into L and U bends to protect edges or can be thermoformed to protect frames.

HANDRAILS114/139

They are ergonomic, and also provide wall protection. SPM handrails are made from a combination of PVC and aluminium and cater for all your needs: they ensure mobility and provide security, and can be adapted to fit any building (curved surfaces, corners at variable angles, service ducts, staircases...).

SPECIFIC PROTECTION140/147

- Individual protection 140/143
- Industrial protection 144/147

TECHNICAL SOLUTIONS148/153

- Solutions for panels: thermowelding, thermoforming, fixing 148/149
- Solutions for handrails 150/151
- Tools 152/153

PHOTO BOOK154/177

COLOUR AVAILABILITY SUMMARY CHART178/181

DOCUMENTS AND SAMPLE CARDS AVAILABLE182/183

ALPHABETIC INDEX 184

ABOUT US

A GERFLOR GROUP COMPANY

• **Wall Protections and Handrails Specialist**

SPM, a Gerflor Group company, offers solutions for protecting walls, doors and corners and for assisting people moving around in compliance with legislation applicable to public buildings.

Present in **education, healthcare, housing, sport, hospitality and industry markets**... and aware of the requirements of each, SPM develops products that are resistant to shocks, scratches, cleaning agents and disinfectants, Bs2d0 fire-rated and easy-to-install while adopting an environmentally responsible approach.

SPM wall protections and handrails blend seamlessly into all locations thanks to a **wide choice of colours and designs**.

Because providing you with solutions perfectly tailored to your needs has been our priority for 40 years, we have established sales divisions near you. In France and in other countries, your SPM contacts know your infrastructures, your requirements, those relevant to your sector of activity and can answer any technical questions you may have.



• **Near you across the world**

SPM has a very strong presence in France. For other markets, the company benefits from the experience and performance of a sales network developed by GERFLOR Group in more than 100 countries.



• **An attentive and responsive team**

- Tools to help you make your choice (brochures, technical specifications, colour charts, etc.)
- Experts present on-site to give you the best advice for your specific project
- Price offers and estimates calculated according to your precise needs
- An Engineering & Design Office at your service for custom projects
- Attractive pricing terms
- Quick delivery times
- Support with product installation



• **An organizational system designed to support you well**

- Marketing & Communication: responsible for our corporate image and product development, this department coordinates our quality approach across all markets.
- R&D: a true driving force in our business, this department creates, tests and develops protection solutions meeting your expectations.
- Sales Team: our male and female sales representatives have extensive technical knowledge. They assess your needs and adapt their advice accordingly, from invitations to tender through to installation.
- Production and Logistics: this department selects our suppliers from among leading players in each sector. Deploying modern and well-integrated production facilities, it manages all stages from the manufacturing process through to on-site delivery.
- Technical Assistance Support (TAS): our expert consultants visit your sites to give support. They also provide technical training on how to install our products (contact us).



Injection mould - Impact 200 end piece





Decoclean panel
▼

▲
Decoprint panel

▲
Floor / Wall coving

A BACTERIOSTATIC PVC MATERIAL

Our PVC products have been formulated to deliver bacteriostatic performance (prevent bacteria from spreading). The non-porous surface and rounded shape of each product can be credited to our extensive research efforts. The entire SPM range has been specifically designed to ensure easier cleaning and prevent dust and germs from building up. Our products are compatible with the most demanding environments of hospital sector 4. (NOSOCO.TECH laboratories, test reports no. 10053101 and 10053102)

BACTERIO-
STATIC

PROVEN VIRUCIDAL ACTIVITY

SPM handrails act as a shield against hand-borne germs and represent an effective solution for helping prevent microorganisms from spreading and hospital-acquired infections from developing. Laboratory tests carried out by skilled virologists have shown that SPM's PVC handrails offer 99.96% intrinsic virucidal activity against human coronavirus HCoV-229E after a contact time of two hours! By way of comparison, the virus is still active on a 304L stainless steel surface after five hours. (Certificate available on request).

VIRUCIDAL*
99.96%

*virucidal activity against human coronavirus HCoV-229E according to ISO 21702

ARE YOU LOOKING FOR 100% BACTERICIDAL PERFORMANCE?

DELIVERING LONG-TERM PROTECTION AGAINST BACTERIA IS TOP OF THE SPM PRIORITY LIST!

Our bactericidal treatment process offers one of the highest performance levels. The results of our tests on several strains prove its ability to eliminate bacteria (including certain strains causing hospital-acquired infections).

BACTERICIDAL

Staphylococcus aureus	100% eliminated ⁽¹⁾
Escherichia coli	100% eliminated ⁽¹⁾
Salmonella enterica subsp.	100% eliminated ⁽¹⁾
Mycobacterium smegmatis	100% eliminated ⁽¹⁾
MRSA	99.99% eliminated
Listeria monocytogenes	99.99% eliminated
Enterococcus hirae	99.99% eliminated

(1) 99.999% / (2) 99.997% / (3) 99.996%
Intertek analysis report CHL-R16-1026A, according to ISO 22196

On request, SPM can carry out bactericidal treatment on Decochoc and Decoclean panels in every colour, including the entire range of PVC handrails. Contact us for details!

HYGIENE AND MICROBIOLOGICAL DECONTAMINATION

SPM commissioned the hospital hygiene department of the Pasteur Institute laboratory in Lille, France, to examine the cleaning and decontamination performance of its products. The tests prove that SPM products, when cleaned with the standard methods, detergents and disinfectants used in hospitals, are capable of withstanding such cleaning products, produce effective levels of decontamination performance and are suitable for use in hospital environments, even in areas featuring the greatest risk of infection (risk groups 3 and 4). Full detailed reports are available on request. (Pasteur Institute Lille (France) test reports no. NC/0510506M, 0500506M and 1100908M)

ANTIBACTERIAL
100%

99% of bacteria eliminated after 24:00**
**according to JIS Z 2801 on staphylococcus aureus



◀ Decoclean panel with bend

▲ Floor / Wall coving

CONTRIBUTING TO AIRBORNE PARTICULATE CLEANLINESS

Our DECOCLEAN smooth wall protection panel **has achieved ISO Class 5 certification according to ISO 14644-1** (Fraunhofer GE test report no. 1903-1106-4). Tests prove that this panel is **suitable for installation in cleanrooms and associated controlled environments**; rooms where airborne particulate contamination must be controlled in a manner to minimise the introduction, generation and retention of particles inside the space:

- Life sciences: pharmaceuticals, biotechnology, cosmetics, food & drink, etc.
- Leading-edge technology: aerospace, electronics, etc.



NUCLEAR DECONTAMINATION

DECOCHOC and DECOCLEAN wall protection panels have been tested according to DIN 25415 / ISO 8690 and awarded the **"Excellent" rating for their ability to decontaminate radioactively contaminated surfaces.**



CHEMICAL RESISTANCE

SPM products feature a specific formulation to withstand the main types of cleaning materials, disinfectants and antiseptic products commonly used in public buildings and healthcare facilities. SPM draws on the expertise of independent laboratories.

(ANIOS laboratory, test report no. 17242.04/219, BIOQUELL® test report no. TD041-003-14)



100% of bacteria eliminated
30 minutes
after decontamination

COMPLIANCE WITH FOOD CONTACT REQUIREMENTS

The tests performed on SPM's DECOCHOC and DECOCLEAN panels have proven their compliance with European Regulation (EC) no. 1935/2004 for contact with food.

(Intertek test report no. AFRAJ15002186-M1)



GLOBAL SOLUTION FOR PERFECT HYGIENE AND WATERTIGHTNESS

All SPM panels are made of antibacterial PVC, meaning that they are easy to clean and can be installed:

- From floor to ceiling with welded joints
- In right or rounded angles, irrespective of the degree or radius
- Above the coving of PVC floor coverings

For a reliable watertightness, SPM has a range of welding rods matched to the colours of SPM profiles, allowing you to thermoweld one panel to another.

SPM and GERFLOR also provide a global solution for absolute watertightness and reliable junction: hot welded joints between the coving of the floor covering and the wall panel.

This system is optimised to work with the exclusive GERFLOR Corner System, and is particularly recommended for operating rooms and other rooms requiring a high level of hygiene.



RESISTANCE AND PROTECTION



IMPACT RESISTANCE

SPM products are engineered to at least withstand impacts greater than 320 kg at 3 km/h. Our panels deliver impact resistance performance greater than 15 joules according to NF EN ISO 6603-1 and 300 joules according to ASTM F476-84.



SCRATCH RESISTANCE

Our solid colour panels are textured with the "Optimixt" grain to conceal scratches. Their stylish and attractive design guarantees easy cleaning. (Scratch resistance > 10N according to NF EN 14565)



FIRE RATING Bs2d0

Irrespective of its colour, the formulation for SPM's antibacterial PVC incorporates Bs2d0 fire reaction performance according to European standard NF EN 13501-1. To achieve this rating, all our products (profiles, accessories) are subjected to a complete set of tests by an approved laboratory.



STAIN RESISTANCE

Our Decochoc wall protection panels offer superior stain resistance, even with the most aggressive stains, such as betadine, eosin and alcohol-based iodine solutions. (Tests performed according to NF EN ISO 26987).



A RANGE THAT RESPECTS THE ENVIRONMENT

European REACH Regulations

European Registration, Evaluation, Authorisation and restriction of Chemicals (REACH) regulations are intended to improve protection standards for human health and the environment. They require all manufacturers to declare any chemical substances listed as hazardous that may be used in the composition of their products. None of the substances used to manufacture SPM products appears in the list drawn up under the REACH regulations.

Health, Quality and Environmental guidelines:

SPM products are suitable for use in building projects adopting High Quality Environment (HQE) standards.



SPM manufactures wall protection products and handrails from non-polluting and eco-friendly materials. All SPM products exceed the requirements of current regulations.

EXEMPLARY COMPOSITION

• Non-polluting materials


SPM PVC products contain no heavy metals such as lead, cadmium, arsenic, tin, etc. and are PBT-free (Persistent Bioaccumulative Toxins) / BPA-free (Bisphenol A).

• Calcium-zinc thermal stabilisation

SPM has chosen to use calcium-zinc stabilisation, which is non-toxic and poses no environmental threat. SPM is therefore ahead of the game, emphasising yet again its commitment to sustainable development.

• Air quality

Our products are tested according to the norms serie ISO 16000-6. They have a rate of less than 100 µg/m³ over 3 days, that is to say a tiny rate compared to the required threshold. Our panels were rewarded with **Greenguard Gold label** for their low emission ensuring good air quality indoor.



According to French regulations
* Information about the emission level of volatile substance in inside air, involving a toxic risk by inhalation, on a scale from A+ (very low emissions) to C (high emissions).



RECYCLING

Our materials are mainly PVC and aluminium and thus 100% recyclable. To this end, all the offcuts from the manufacturing process are also recycled.

REDUCED ENVIRONMENTAL IMPACT DURING INSTALLATION AND IN USE

• Adhesives

We recommend the use of SPM adhesives when installing our products, either a water-based acrylic adhesive or a multipurpose adhesive sealant on a MS polymer base. These adhesives use no solvents and thus present no threat to either the users' health or the environment.



• Reduced levels of waste through custom-made lengths

SPM offers a pre-cutting service (standard lengths from the catalogue or made-to-measure) that eliminates wasteful offcuts.

• Cleaning and maintenance

The products are easy to clean and reduce the consumption of both water and cleaning products.

• Durability

SPM solutions extend infrastructural life spans and also extend considerably the intervals between wall repair and renovation work.

ENVIRONMENTAL AND HEALTH PRODUCT DECLARATION

The EPD for the wall protection panels in PVC is available on request.

(Kalei report Environmental Product Déclaration in accordance with standards NF EN ISO 14025, NF EN 15804+A1 and its national complement NF EN 15804/CN)

SPM CONTINUES TO INNOVATE FOR YOU



IN A NUMBER OF OTHER DOMAINS

Specialist in wall protections and handrails for 40 years, SPM develops innovative and decorative solutions to protect, enhance and ensure the sustainability of your walls and doors.

SPM IN BIMOBJECT

Always attentive to the needs of its customers and partners, SPM offers the opportunity to download BimObject in Revit and ArchiCAD covering its entire range.

A NEW COLOUR CHART

A new design and trendy colour chart with 47 colours and decors created with the help of our partner architects and colourists in order to offer you an even wider choice:

- Basalt black, Magnolia pink,
- 3 metallic **Decosmic** colours, perfect as part of a contemporary decor scheme,
- 7 **Decowood** decors for a designer feel with warmth,
- 4 **concrete or metalized** decors for **Decotrend**, essential decor looks!



DECOPRINT PRINTED PANELS

Decoprint printed panels, created by SPM, protect and personalize your walls and doors using digital printing (reproduction of photos, drawings, messages, logos, etc.). It is the ideal decoration solution adding an aura of elegance and originality to your establishment.

ACCESSIBILITY

We have developed numerous solutions to meet accessibility requirements:

- **Adjustable and variable 3D angle Rapid'Angle®** to fit in all stair-cases layouts and to all angles from 80° to 180°.
- **The option of high visual contrast** using a well thought-out range of colours that provide wall protection in neutral and natural shades against which our handrails, in their acid, bright colours, stand out and are immediately visible to users with impaired vision.
- **Powerful visual identifiers** based on outline shapes and inlays that customize doors and walls and make it easier to recognise places and find one's way, especially for those with impaired cognition.
- **Tactile identifiers** are available for Escort handrails using their unique design of finishing strip that can be customized on request.
- **A double bracket** for the simple installation of Escort handrails at two heights, one standard, the other for children and those using wheelchairs.



DECOCHOC H₂O PANELS

NEW COLOURS

The innovative solution for protecting walls and doors in wet rooms. The formulation and grained surface are perfectly suited to wet areas and provide total and long-lasting watertightness. It has been certified by a Technical Approval from CSTB.



PROTECTION HANDRAILS ESCORT'DUO & LINEA'DUO

NEW

Escort'Duo and Linea'Duo protection handrails are designed to ensure the double purpose of wall protection and handrail, in corridors with high impacts of wheeled equipments. They are provided with bactericidal joints.

Ideal for all public buildings (hospitals, clinics, reeducation centres, homes for the elderly), they provide different choices:

- Select the shape of the upper part of the handrail: round with Escort'Duo or trilobed with Linea'Duo.
- Select the one colour or the two-colour option to differentiate the handrail from the wall protection rail.



The bactericidal joints used with our handrails help in the fight against the transmission of hand-borne contamination, which is responsible for the great majority of hospital acquired infections.

(Nosoco. tech laboratories, test report n°08112803)

Most of our profile strips come with a peel-off protective film to protect them from any marks whilst work is in progress. When left on until the time of acceptance, this film prevents the need for complete cleaning of our products.

SPECIFIC SOLUTIONS PER SECTOR

+ HOSPITALS - CLINICS

• Priority to Hygiene

In operating theatres, cleanrooms, laboratories... hygiene has to be the number one priority more than anywhere else. We develop antibacterial and bacteriostatic PVC that do not collect germs and are resistant to disinfectants.

• Impact resistance

Each corridor, each passage way has its own traffic. Our wall protection systems and handrails fit in with different impact intensities or wear, from occasional passage to heavy traffic.

• Easy maintenance

Non-porous surfaces and curved shapes have been developed with hygienists to prevent germ incrustation. Our PVC is resistant to solvents, diluted acids and industrial detergents.

• Simplified installation

Our products are designed to be easily installed and to limit noise and chemical pollution during the installation: easy and quick fitting together, odourless glues.



RETIREMENT HOMES - DISABILITY CENTERS

• Comfort

As the bedroom becomes the patient's main living room, the risks related to moving furniture is increased (beds, wheelchairs, service trolleys, chairs...). SPM wall protections protect against wear, whilst providing well-being and comfort.

• Ergonomics

Our handrails are especially designed for a perfect handgrip and provide safe support for users.

• Living environment

SPM wall protections and handrails enhance interiors whilst offering a warmer living environment, and contribute to well-being of the elderly. Pastel or bright, colours will fit perfectly into the existing décor and facilitate visual guidance.



EDUCATION

• Heavy traffic


In public areas, the heavy and repeated flow of pupils or equipment creates premature and intensive wear and tear. So that these living and working areas are friendly and resistant, SPM has designed ranges of wall protections to meet these requirements.

• Maintenance

SPM protection systems reduce wear and tear as well as impacts on walls and extend the lifetime of buildings. Easy to clean and maintain, they contribute towards reducing maintenance costs.

• Aesthetic

SPM solutions help you to create and preserve pleasant settings, colourful and fun décors which encourage the well-being of toddlers. They enhance your premises whilst maintaining them in good condition.



INDUSTRY

• Controlled environment

In the pharmaceutical sector, especially in cleanrooms, the control of bacteriological contamination is essential. SPM develops solutions that meet these requirements.

• High impact resistance

High-load trolleys pass through corridors, technical areas, logistical premises. SPM wall protections provide unmatched impact resistance and protect premises for a long time.

• Quick installation


On-going activity must not be interrupted. SPM wall solutions are easy and quick to install, ensuring very short period of downtime of the premises.



HOTELS - CATERING

• Enhance your image

In an environment constantly and heavily frequented by people, a refined and welcoming décor adds to the appeal of your establishment. SPM's decorative and easy-to-maintain solutions preserve walls and doors against wear and tear due to luggage, cleaning trolleys, chairs and tables, traces of soiling around handles, etc. They can provide a decorative touch or blend discreetly into the background.



HOUSING

• Protecting infrastructure

Given high foot traffic and potential soiling or damage, it is essential to protect building infrastructure. SPM solutions preserve premises durably against impacts on walls, doors and corners and facilitate maintenance and cleaning. They contribute to a pleasant and safe living environment and meet relevant health and safety requirements.



SPORT

• Large width protection

In gymnasiums, impacts (of balls, sticks, studs...) can appear anywhere. So it is important to protect the more exposed areas: lower parts of walls, doors, angles, in order to keep the premises in a good state. In other areas where physical activities are practiced (dancing, fitness and martial arts), the wall protection protects from wear and tear and makes maintenance easier.

• Wet areas

The cloakrooms and notably the shower areas have to be protected against the damaging effects of moisture: corrosion, moulds. SPM solutions contribute to making these areas more watertight: welded panels and doors protected with bends and cutouts.





HERE NOTHING
IS LEFT TO
CHANCE

HOSPITALS
CLINICS



HOSPITALS - CLINICS


WALL PROTECTION										CORNER		PROTECTION		DOOR PROTECTION				HANDRAILS						IP*																												
Linea'Punch Neo	Impact 200 / Combo'Punch 200	Impact 120 / Combo'Punch 125	Impact 60 / Combo'Punch 100D	Contact 350	Contact 200 / Combo'Clad 200	Combo'Clad 150	Decochoch (edge to edge, silicone joint)	Decochoch (thermowelded)	Decosmic	Decowood / Decotrend - Panels	Decoclean	Decochoch, Decowood and Decotrend H2O	Decochoch Staro	Combo'Bedkit	Decofresc - Decorative frescoes	Decoprint	Plac'Inox	Cornea	Corneaflex	Combo'Corner	Linea'Flex	Protecta 2 / Combo'Flex	Profila / Combo'Line	Decosmic corner L-bent (in line with walls)	Decowood / Decotrend corner L-bent (in line with walls)	Profil'Inox	Complete doors (2 sides)	½ height door	Foot-height door	½ height decorative door	Handplates	½ height door - Inlaid signage	Bendings, edges and frames	Plac'Inox	Escort'Duo	Linea'Duo	Performer 2 / Combo'Duo	Starline - PVC sheathed	Starline - Anodised	Linea'Touch+ - PVC sheathed	Linea'Touch - PVC sheathed	Linea'Touch LED- Pvc Sheathed	Linea'Touch - Decowood	Linea'Touch LED- Decowood	Linea'Touch - Anodised	Linea'Touch LED- Anodised	Escort - PVC sheathed	Escort - Decowood	Escort - Anodised	Elasto'Flex 100V	Elasto'Punch 200E	Elasto'Punch 100D

[illegible][illegible][illegible][illegible][illegible][illegible][illegible][illegible][illegible]








CONTRIBUTING
TO RESIDENT
WELL-BEING

.....
RETIREMENT HOMES
DISABILITY
CENTERS



RETIREMENT HOMES - DISABILITY CENTERS

WALL PROTECTION																	CORNER	PROTECTION	DOOR PROTECTION				HANDRAILS							IP*																					
Linea' Punch Neo	Impact 200 / Combo' Punch 200	Impact 120 / Combo' Punch 125	Impact 60 Combo' Punch 100D	Contact 350	Contact 200 / Combo' Clad 200	Combo' Clad 150	Decochoc (ledge to edge, silicone joint)	Decochoc (thermowelded)	Decosmic 	Decowood / Decotrend - Panels	Decoclean	Decochoc, Decowood and Decotrend H2O 	Decochoc Staro 	Combo' Bedkit	Decofresc - Decorative frescoes	Decoprint	Plac' Inox	Cornea	Corneaflex	Combo' Corner	Linea' Flex	Protecta 2 / Combo' Flex	Profila / Combo' Line	Decosmic corner L-bent (in line with walls)	Decowood / Decotrend corner L-bent (in line with walls)	Profil' Inox	1/2 height door	Foot-height door	1/2 height decorative door	Handplates	1/2 height door – Inlaid signage	Bendings, edges and frames	Plac' Inox	Escort'Duo 	Linea'Duo 	Performer 2 / Combo'Duo	Starline - PVC sheathed	Starline - Anodised	Linea'Touch+ - PVC sheathed	Linea'Touch - PVC sheathed	Linea'Touch LED - Pvc sheathed	Linea'Touch - Decowood	Linea'Touch LED - Decowood	Linea'Touch - Anodised	Linea'Touch LED - Anodised	Escort - PVC sheathed	Escort - Decowood	Escort - Anodised	Elasto'Flex 100V	Elasto'Punch 200E	Elasto'Punch 100D

Moderate traffic corridor	●	●	○		●	●		●		●		○			●		●	●	●	●	○	○	○		●	○	●		●	●					●		●	●	○		●	○										
Elevator	●	●	●	○				●		●		○			●											○																										
Elevator landing	●	●	●	○				●		●		○			●		●	●	●	○			●		○												●			●	○			●								

[illegible][illegible][illegible][illegible][illegible]

* Industrial protection








A WELCOMING
ENVIRONMENT
FOR PUPILS

.....
EDUCATION



EDUCATION

WALL PROTECTION																	CORNER		PROTECTION		DOOR PROTECTION				HANDRAILS							IP*																		
Linea' Punch Neo	Impact 200 / Combo' Punch 200	Impact 120 / Combo' Punch 125	Impact 60 / Combo' Punch 100D	Contact 350	Contact 200 / Combo' Clad 200	Combo' Clad 150	Decochoc (ledge to edge, silicone joint)	Decochoc (thermowelded)	Decosmic 	Decowood / Decotrend - Panels	Decochoc, Decowood and Decotrend H2O 	Decochoc Staro 	Decofresc - Decorative frescoes	Decoprint	Decokid - Educational Panels	Plac'Inox	Cornea	Corneaflex	Combo' Corner	Linea' Flex	Protecta 2 / Combo' Flex	Profilta / Combo' Line	Decosmic corner L-bent (in line with walls)	Decowood / Decotrend corner L-bent (in line with walls)	Profil' Inox	1/2 height door	Foot-height door	1/2 height decorative door	Handplates	1/2 height door - Inlaid signage	Bendings, edges and frames	Plac'Inox	Escort'Duo 	Linea'Duo 	Performer 2 / Combo'Duo	Starline - PVC sheathed	Starline - Anodised	Linea' Touch+ - PVC sheathed	Linea' Touch - PVC sheathed	Linea' Touch LED - Pvc sheathed	Linea' Touch - Decowood	Linea' Touch LED - Decowood	Linea' Touch - Anodised	Linea' Touch LED - Anodised	Escort - PVC sheathed	Escort - Decowood	Escort - Anodised	Elasto'Flex 100V	Elasto'Punch 200E	Elasto'Punch 100D


[illegible][illegible][illegible][illegible][illegible]

* Industrial protection



PROTECTING AND ENHANCING INFRASTRUCTURE

OFFICES
HOTELS
CATERING
HOUSING



OFFICES - HOTELS - CATERING - HOUSING

WALL PROTECTION										CORNER		PROTECTION		DOOR PROTECTION			HANDRAILS						IP*	
Linea'Punch Neo										Cornea		Protecta 2 / Combo'Flex		Complete doors (2 sides)			Escort'Duo						Elasto'Flex 100V	
Impact 200 / Combo'Punch 200										Corneaflex		Profila / Combo'Line		1/2 height door			Linea'Duo						Elasto'Punch 200E	
Impact 120 / Combo'Punch 125										Combo'Corner		Decosmic corner L-bent (in line with walls)		Foot-height door			Performer 2 / Combo'Duo						Elasto'Punch 100D	
Impact 60 / Combo'Punch 100D										Linea'Flex		Decosmic corner L-bent (in line with walls)		1/2 height decorative door			Starline - PVC sheathed							
Contact 350										Decokid - Educational panels		Decowood / Decotrend corner L-bent (in line with walls)		Handplates			Starline - Anodised							
Contact 200 / Combo'Clad 200										Plac'Inox		Profil'Inox		Bendings, edges and frames			Linea'Touch+ - PVC sheathed							
Combo'Clad 150														Plac'Inox			Linea'Touch - PVC sheathed							
Decochoc (ledge to edge, silicone joint)																	Linea'Touch - PVC sheathed							
Decochoc (thermowelded)																	Linea'Touch LED- PVC sheathed							
Decosmic																	Linea'Touch - Decowood							
Decowood / Decotrend - Panels																	Linea'Touch LED- Decowood							
Decochoc, Decowood and Decotrend H2O																	Linea'Touch - Anodised							
Decochoc Staro																	Linea'Touch LED- Anodised							
Decofresc - Decorative frescoes																	Escort - Decowood							
Decoprint																	Escort - Anodised							
Decokid - Educational panels																								
Plac'Inox																								

[illegible][illegible][illegible][illegible]

* Industrial protection



EFFECTIVENESS
AND COMPLIANCE
WITH STANDARDS

.....
INDUSTRY
SPORT



EFFECTIVENESS & COMPLIANCE WITH STANDARDS

INDUSTRY - SPORT

INDUSTRY

WALL PROTECTION																	CORNER		PROTECTION		DOOR PROTECTION					HANDRAILS							IP*																		
Linea'Punch Neo	Impact 200 / Compo'Punch 200	Impact 120 / Combo'Punch 125	Impact 60 / Combo'Punch 100D	Contact 350	Contact 200 / Combo'Clad 200	Combo'Clad 150	Decochoc	Decosmic	Decowood / Decotrend - Panels	Decoclean	Decochoc, Decowood and Decotrend H ₂ O	Decochoc Staro	Decofresc - Decorative frescoes	Decoprint	Decokid - Educational panels	Plac'Inox	Cornea	Corneaflex	Combo'Corner	Linea'Flex	Protecta 2 / Combo'Flex	Profila / Combo'Line	Decosmic corner L-bent (in line with walls)	Decowood / Decotrend corner L-bent (in line with walls)	Profil'Inox	Complete doors (2 sides)	½ height door	Foot-height door	½ height decorative door	Handplates	½ height door - Inlaid signage	Bendings, edges and frames	Plac'Inox	Escort'Duo	Linea'Duo	Performer 2 / Combo'Duo	Starline - PVC sheathed	Starline - Anodised	Linea'Touch+ - PVC sheathed	Linea'Touch - PVC sheathed	Linea'Touch LED - Pvc sheathed	Linea'Touch - Decowood	Linea'Touch LED - Decowood	Linea'Touch - Anodised	Linea'Touch LED - Anodised	Escort - PVC sheathed	Escort - Decowood	Escort - Anodised	Elasto'Flex 100V	Elasto'Punch 200E	Elasto'Punch 100D

LIFE SCIENCES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
Laboratory, cleanroom, airlocks																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

SPORT

WALL PROTECTION																	CORNER		PROTECTION		DOOR PROTECTION				HANDRAILS						IP*																				
Linea'Punch Neo	Impact 200 / Compo'Punch 200	Impact 120 / Combo'Punch 125	Impact 60 / Combo'Punch 100D	Contact 350	Contact 200 / Combo'Clad 200	Combo'Clad 150	Decochoc	Decosmic	Decowood / Decotrend - Panels	Decoclean	Decochoc, Decowood and Decotrend H ₂ O	Decochoc Staro	Decofresc - Decorative frescoes	Decoprint	Decokid - Educational panels	Plac'Inox	Cornea	Corneaflex	Combo'Corner	Linea'Flex	Protecta 2 / Combo'Flex	Profila / Combo'Line	Decosmic corner L-bent (in line with walls)	Decowood / Decotrend corner L-bent (in line with walls)	Profil'Inox	Complete doors (2 sides)	½ height door	Foot-height door	½ height decorative door	Handplates	½ height door - Inlaid signage	Bendings, edges and frames	Plac'Inox	Escort'Duo	Linea'Duo	Performer 2 / Combo'Duo	Starline - PVC sheathed	Starline - Anodised	Linea'Touch+ - PVC sheathed	Linea'Touch - PVC sheathed	Linea'Touch LED- PVC sheathed	Linea'Touch - Decowood	Linea'Touch LED- Decowood	Linea'Touch - Anodised	Linea'Touch LED- Anodised	Escort - PVC sheathed	Escort - Decowood	Escort - Anodised	Elasto'Flex 100V	Elasto'Punch 200E	Elasto'Punch 100D

HEAVY TRAFFIC AREAS																																															
Circulation																																															
Stairs																																															
SPORTS AREAS																																															
Gymnasium																																															
Fitness and body building room																																															
PUBLIC AREAS																																															
Cafeteria, bar																																															
ADMINISTRATION / ADMINISTRATIVE OFFICES																																															
Cloakroom																																															
WET ROOMS																																															
Shower / Sanitary arrangements																																															








A PALETTE OF 33 COLOURS

LET WALL PROTECTION PLAY A DYNAMIC ROLE IN DECORATION



COLOUR
RANGE

NATURAL

















			
0001 Chalk LRV 85.8	0031 Alum LRV 72.6	0032 Flint LRV 43.0	0036 Basalt LRV 5.0
			
0011 Pebble LRV 56.2	0002 Gravel LRV 53.4	0003 Clay LRV 33.3	0033 Slate LRV 6.5
			
0014 Cinnamon LRV 40.1	0009 Sienna LRV 27.2	0010 Bark LRV 16.3	0004 Granite LRV 25.1
			
0006 Ivory LRV 82.5	0007 Wicker LRV 70.9	0008 Sand LRV 52.5	0005 Schist LRV 16.3
			
0013 Greige LRV 40.7			

SPM OFFERS...

... a range of colours designed with the help of architects, interior designers, users, etc. The colour chart with 33 colours, from the most sober to the most daring, gives a new identity to interior designs whilst blending perfectly with other decorative elements such as floors, walls, doors, etc.

This palette brings together neutral, sober, mineral shades that blend naturally with architectural design and vivid, refreshing, full-bodied and youthful colours. Tinted greys provide subtle, muted ambiances. Let SPM wall protection play a dynamic role in the aesthetic appearance of your facility.

COLOUR

			
0021 Straw LRV 72.8	0022 Apricot LRV 56.7	0027 Melon LRV 35.9	0028 Poppy LRV 16.7
			
0034 Magnolia LRV 53.6	0015 Lavender grey LRV 34.7	0030 Iris LRV 17.4	0029 Garnet LRV 11.4
			
0016 Glacier LRV 57.6	0018 Azure LRV 44.5	0017 Bluebell LRV 36.9	0020 Denim LRV 16.8
			
0024 Bamboo LRV 52.4	0023 Meadow LRV 53.6	0025 Emerald LRV 29.3	0019 Ultramarine LRV 28.4

Colours are not contractually binding.

PLEASE NOTE

- LRV (Light Reflectance Value) measures based on Decochoc panel.
- In order to speed up delivery of your orders, we have adapted our colour range in line with our products. Most of our products are available in all 33 colours in the range, or 31.
- Each product display page shows the numbers of colours available and there is a summary table at the end of the guide for all the products (p. 178 to 181).

DECOWOOD RANGE

7 WOOD EFFECT DECORS



A COORDINATED RANGE

SPM offers a full range of decorative wood decors for use in those establishments that wish to combine wall protection and handrails with the warmth of wood.


This range consists of products matched to various requirements, providing safety for all with the Escort, Linea and Starline handrails, wall and door protection with Decowood protection panel and corner protection with the bent Decowood panel.



A WIDE CHOICE OF WOOD DECORS


The range has been expanded with two new wood decors, chosen to suit all interiors.

To the five existing decors Maple, Beech, Light Oak, Wenge and Stripped Pine, we have added Brown Cedar and Smoky Cedar.




COLOUR
RANGE


Linea'Touch Decowood Handrail



Escort Decowood Handrail



Starline Decowood Handrail



Adhesive corner protector in bent Decowood




Decowood protection panels



Colours are not contractually binding.


DECOTREND RANGE



4 TREND DECORS



0050 Brushed aluminium LRV 41.4



0051 Composite LRV 16.0



0052 Light concrete LRV 45.8




0053 Medium concrete LRV 31.0

TO COMBINE DECORATION AND PROTECTION

SPM has designed some new decors to inspire the creation of individual, distinctive and damage resistant spaces. The overall approach is modern and urban. These decors lend themselves to some astonishing visual effects:

- a shaped perspective view with “Composite”
- a striking appearance of “Brushed Aluminium”
- a resolutely material effect with “Light concrete” and “Medium concrete”.

Starline Decotrend Handrail



Adhesive corner protector in bent Decotrend




Decotrend decorative protection panel



Colours are not contractually binding.

DECOSMIC PANELS



3 DECOSMIC COLOURS



0080 Silver LRV 42.4



0081 Copper LRV 20.9



0082 Gold LRV 27.3

The metallic colours of DECOSMIC panels, combining protection with contemporary design, embellish your spaces in a stylishly modern way and create a unique look for your establishment.

- Silver brings elegance, modernity and simplicity.
- Copper, very on-trend, is perfect for creating a contemporary decor look.
- Gold lights up your spaces, enhancing them and creating warmth.

Decosmic protection and covering panel

Metallic look



Adhesive corner protector in bent Decosmic



Colours are not contractually binding.

EARLY CHILDHOOD

Decofresc decorative protection frescoes

Savannah theme



Picture 0



Picture 1



Picture 2



Picture 3

Maritime theme



Picture 0



Picture 1



Picture 2



Picture 3

Mountain theme



Picture 0



Picture 1



Picture 2



Picture 3

Decokid educational panels



1. I cross the road at a pedestrian crossing.



2. Early to bed, early to rise.



3. 30 mph, that's the urban speed limit.



4. I always say, 'Hello'.



5. I always put my rubbish in the bins provided.



6. I always wash my hands before eating.



7. I always wear my seat belt in the car.



8. I take breaks from my video games.



9. I always wash my hands after using the toilets.



10. No pushing.



11. I never leave the tap running.

Colours are not contractually binding.


SAFY RANGE “INDIVIDUAL PROTECTION”

The SAFY range is all about individual protection and SPM has selected colours with two potential requirements in mind:

- The wish to make premises safe in a discreet way with the neutral colours Swan, Fawn and Dolphin,
- The need to provide warning signals while also enlivening spaces with bright Canary.


SAFY’CORNER

Safy’Corner 90° adhesive cushioning corner protector



SAFY’DOOR

Safy’Door door finger protection



Colours are not contractually binding.

A PRACTICAL GUIDE


THE SOLUTIONS

SPM has worked closely with its customers, in order to understand their specific needs. This partnership has led to the development of a complete range of solutions that cater for your every need.

Whether you need to protect walls from impact and wear, shield areas such as angles and doors that are prone to damage, or install handrails that provide both protection and aid mobility – whatever you require, SPM has the total solution for you.

Description
States all the details of the concerned product.

Applications
By detailing the practical applications of each product we can help you to make the right choice for your particular needs.



FOR ANY ADVICE
PLEASE CONTACT US

Range of colours
See all the colours available for the product at a glance.

Technical drawings
This enables you to see everything clearly (scale 1: for most of the products): the strong points and particulars of each of our products, including the mounting systems.

Specification
It provides you with the necessary information about specifications, such as technical information, a complete description and fitting instructions.

Product overview
This provides you with all the information concerning a particular product, as well as the available options.

CLASSIFICATION FOR PROTECTION REQUIREMENTS

A COLOUR CODE FOR EVERY APPLICATION

Solutions for "protection" vary according to which areas of a building are subjected to impact, or intensive use by people and mobile equipment. We have established a classification system for the various applications and have given them a colour code that can be used as a guide throughout our catalogue.

- RED > FOR HEAVY TRAFFIC AREAS**
Intensively used areas that are subjected to hard impact
- ORANGE > FOR MODERATE TRAFFIC AREAS**
Standard intensity areas that are repeatedly subjected to impact
- BLUE > FOR LIGHT TRAFFIC AREAS**
Low intensity areas that are subjected to light impact and localised wear

CONVENIENT INTERNET & BIMOBJECT

All technical informations (specifications, scale 1 section drawings and installation instructions) are available to download on our website: www.spm-international.com
Most of the products are available on BIMobject.



INSTALLATION PROCEDURES

To help with the installation of our products, the installation procedures guide is available upon request.



COLOUR
RANGE

WALL PROTECTION



All public buildings have similar difficulties: premature deterioration together with wear and tear of their premises.

Corridor walls, corners and doors are constantly knocked by trolleys and are damaged by continuous pedestrian traffic.

In operating theatres and cleanrooms asepsis is absolutely imperative.

SPM has developed three ranges of products that have been tested in order to offer you the most appropriate solutions – wall protection rails, protection plates and the decorative protection and covering panels.

All are resistant to impact, germs and cleaning products. They are made from solid-colour and antibacterial PVC therefore the colour will not alter with cleaning or time.



WALL PROTECTION

PROTECTION RAILS AND PLATES



LINEA'PUNCH NEO p.52-53
Wall protection rail
Height 180 mm



IMPACT 200 p.54-55
Wall protection rail
Height 200 mm



IMPACT 120 p.54-55
Wall protection rail
Height 120 mm



IMPACT 60 p.54-55
Wall protection rail
Height 60 mm



COMBO'PUNCH 200 p.56-57
Wall protection rail
Height 200 mm




COMBO'PUNCH 125 p.56-57
Wall protection rail
Height 125 mm




COMBO'PUNCH 100D p.58
Wall protection rail
Height 100 mm




COMBO'BEDKIT p.59
Vertical bedhead
protection




CONTACT 350 p.60-61
Protection plate
Height 350 mm




CONTACT 200 p.60-61
Protection plate
Height 200 mm



COMBO'CLAD 200 p.62-63
Protection plate
Height 200 mm










COMBO'CLAD 150 p.62-63
Protection plate
Height 150 mm




PLAC'INOX p.86
Protection plate




	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
LINEA'PUNCH NEO		Wall protection rail	PVC	31 colours
IMPACT		Wall protection rails	PVC	31 colours
COMBO'PUNCH		Wall protection rails	PVC	31 colours
COMBO'BEDKIT		Vertical bedhead protection	PVC + aluminium	31 colours
CONTACT		Protection plates	PVC	31 colours
COMBO'CLAD		Protection plates	PVC	31 colours
PLAC'INOX		Protection plate	Stainless steel	Brushed


PROTECTION AND COVERING PANELS




DECOCHOC p.64-65
Protection and covering panel
Thickness 2 mm




DECOSMIC p.66-67
Protection and covering panel
metallic look
Thickness 2 mm




DECOWOOD p.68
Decorative protection and
covering panel
Thickness 2 mm




DECOTREND p.69
Decorative protection and
covering panel
Thickness 2 mm




DECOCLEAN p.70-71
Smooth protection and
covering panel
Thickness 2 mm




DECOCHOC H₂O p.72-73
Protection and covering panel
in wet area
Thickness 1.5 mm




**DECOTREND H₂O
DECOWOOD H₂O** p.74-75
Decorative protection and
covering panels in wet area
Thickness 2 mm




DECOCHOC STARO p.76-77
Protection and covering panel
Thickness 1.5 mm




FIN'ALU p.78
Finishing and
jointing profiles




FIN'COLOR p.79
Finishing and
jointing profiles




DECOFRESC p.80-81
Protection and decorative frescoes
Thickness 2 mm



DECOPRINT p.82-83
Customized decorative panel
Thickness 1 mm

















DECOCARE p.84
Hand hygiene panel
Thickness 1 mm



DECOKID p.85
Educational panel
Thickness 1 mm

FIXING p.87
Adhesives, glue, primer...

**FINISHING AND JOINTING
PROFILES** P.87


	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
DECOCHOC		Protection and covering panel	PVC - 2 mm	33 colours
DECOSMIC		Protection and covering panel Metallic look	PVC - 2 mm	3 colours
DECOWOOD		Decorative protection and covering panel	PVC - 2 mm	7 wood effect decors
DECOTREND		Decorative protection and covering panel	PVC - 2 mm	4 trend decors
DECOCLEAN		Smooth protection and covering panel	PVC - 2 mm	5 colours
DECOCHOC H ₂ O		Protection and covering panel in wet area	PVC - 1.5 mm	12 colours
DECOTREND & DECOWOOD H ₂ O		Decorative protection and covering panels in wet area	PVC - 2 mm	4 decors
DECOCHOC STARO		Protection and covering panel	PVC-free - 1.5 mm	9 colours
FIN'ALU		Finishing and jointing profiles	Aluminium	Satin silver anodised
FIN'COLOR		Finishing and jointing profiles	PVC	33 colours
DECOFRESC		Protection and decorative frescoes	PVC - 2 mm	3 themes with 4 pictures each 2 models - 33 colours
DECOPRINT		Customized decorative panel	PVC-free - 1 mm	-
DECOCARE		Hand-hygiene panels	PVC-free - 1 mm	2 models
DECOKID		Educational panels	PVC-free - 1 mm	11 models



NEW
MATTIFIED
FINISH



Linea'Punch Neo // 31 colours



LINEA'PUNCH NEO

WALL PROTECTION RAIL - 180 MM HIGH



APPLICATIONS

The Linea'Punch Neo protection rail is the perfect alliance between impact resistance and design.

Its uncluttered line helps it merge with the decor, and matches perfectly the Linea'Touch handrails for an aesthetic and high-performance solution throughout the building.

Its narrow beveled end pieces are smooth and minimise projection and reduce the distance to door frames, and the wall-hugging profile makes for easy cleaning and maximum hygiene. It is easy and quick to install, thanks to its double clipping.



It provides effective and discreet protection for walls exposed to heavy trolley traffic in corridors, access areas and storage rooms (hospitals, clinics, retirement homes, labs, cleanrooms, hotels, restaurants, schools).

DESCRIPTION

- Model: Linea'Punch Neo protection rail
- Height: 180 mm
- Depth: 25 mm
- Length: 4 m
- Material: 2.5 mm thick PVC, antibacterial and Bs2d0 fire-rated, solid colour
- Surface finish: mattified with central boss
- Fixing components: aluminium brackets (optional: continuous aluminium rail)
- Colours: 31 standard

NOTA


The end piece serves as the first clip.



SPECIFICATION

- Description: flat wall protection rail with a central boss (Linea'Punch Neo as manufactured by SPM) from mattified and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile projects 25 mm, is 180 mm high and 2.5 mm thick. It provides a mattified surface finish and snap-fixes onto aluminium brackets or continuous aluminium rail (optional) made more robust by an exclusive 'omega' shape. The upper and lower parts of the profile are smooth, beveled and edged with strengthened lips to hold the profile tightly against the wall and minimise dust traps. A protective film is specified to minimise cleaning before acceptance. Finish is provided by slim beveled and smooth end pieces (16.5 mm wide). This wall protection rail achieves an impact resistance in excess of 110 Joules, i.e., an impact of more than 320 kg travelling at 3 kmh.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: recommended height of protection rail centreline 0.80 m above floor level for mid-level wall protection or on top of the skirting for low level wall protection. Snap-fixes to aluminium '4-point' brackets spaced at 0.75 m centres or continuous aluminium rail (optional).





Impact 60 // 5 colours*



Impact 200/120 // 31 colours



* and 26 colours on request with a minimum order quantity

IMPACT

WALL PROTECTION RAILS - 200/120/60 MM HIGH



APPLICATIONS



This horizontal protection system features contoured design to bring you the perfect combination of impact resistance and sheer good looks. Fitted at one or two levels, it protects walls exposed to intensive wheeled traffic in corridors, entrances and storage areas (hospitals, clinics, retirement homes, laboratories, cleanrooms, hotels, restaurants, schools).

DESCRIPTION

- Model: Impact 200/120 or 60 wall protection rail
- Height: 200/120 or 60 mm
- Depth: 30 mm
- Length: 4 m
- Material: 3 mm thick PVC, antibacterial and Bs2d0 fire-rated, solid colour
- Surface finish: smooth with decorative grooves
- Fixing components: aluminium brackets (optional: continuous aluminium rail)
- Colours:
 - 31 standard for Impact 200 and 120,
 - 5 standard for Impact 60

NOTA

The end piece serves as the first clip.



SPECIFICATION

- Description: curved wall protection rail (Impact 200/120 or 60 as manufactured by SPM) from smooth and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile projects 30 mm, is 200/120 or 60 mm high and 3 mm thick. It provides a smooth surface finish with decorative grooves and snap-fixes onto aluminium brackets or continuous aluminium rail (optional). A protective film is specified to minimise cleaning before acceptance. Finish is provided by end pieces, external and internal 90° angle pieces in smooth PVC and aluminium jointing blocks.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/ BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range. The colours of accessories are the same as the profile.
- Installation method: recommended height of protection rail centreline 0.80 m above floor level for mid-level wall protection or on top of the skirting for low level wall protection. Snap-fixes onto aluminium brackets spaced at 0.75 m centres or continuous aluminium rail (optional).

WALL
PROTECTION



Combo'Punch 200

Combo'Punch 125



Combo'Punch 200/125
// 4 colours*



*and 27 colours on request with a minimum order quantity.

COMBO'PUNCH

WALL PROTECTION RAILS - 200/125 MM HIGH



APPLICATIONS

These wall protection rails are designed to offer impact protection and scratch resistance against damage caused from both pedestrian and wheeled traffic.



One or two level protection, Combo'Punch 200 and/or 125 protect the walls in corridors, access areas and storage rooms (hospitals, clinics, retirement homes, hotels, restaurants, schools).

NOTA
The end piece serves as the first clip.

DESCRIPTION

- Model: Combo'Punch 200 or 125 wall protection rail
- Height: 200 or 125 mm
- Depth: 25 mm
- Length: 4 m
- Material: 2 mm thick PVC, antibacterial and Bs2d0 fire-rated, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing components: aluminium brackets (optional: continuous aluminium rail)
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.





Combo'Punch 100D
// 4 colours*



*and 27 colours on request with a minimum order quantity.



Combo'Bedkit
// 4 colours*



*and 27 colours on request with a minimum order quantity.

COMBO'PUNCH 100D

WALL PROTECTION RAIL (D-SHAPED) - 100 MM HIGH



APPLICATIONS

Thanks to its 50 mm depth of protection, Combo'Punch 100D keeps wheeled equipments, such as trolleys, carts, wheelchairs, hospital beds, away from the walls and contributes to reduce damages from such impacts especially in corridors and storage areas.



DESCRIPTION

- Model: Combo'Punch 100D wall protection rail
- Height: 100 mm
- Depth: 50 mm
- Length: 4 m
- Material: 2 mm thick PVC, antibacterial and Bs2d0 fire-rated, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing components: continuous aluminium rail
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION

- Description: D-shaped wall protection rail (Combo'Punch 100D as manufactured by SPM) from slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile projects 50 mm, is 100 mm high and 2 mm thick. It snap-fixes onto continuous aluminium rail. Finish is provided by slightly textured end pieces (52 mm wide).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: recommended height of protection rail centreline 0.80 m above floor level for mid-level wall protection or on top of the skirting for low level wall protection. Snap-fixes onto continuous aluminium rail.



Colours available per product:
please see the colour summary hinge

Let discover technical solutions at the end of the guide

COMBO'BEDKIT

VERTICAL BEDHEAD PROTECTION - 750 MM HIGH



APPLICATIONS

This protection has been especially designed to protect walls from bed impacts which are often moved around or elevated in bedrooms in all health buildings.


DESCRIPTION

- Model: Combo'Bedkit bedhead protection
- Height: 750 mm
- Width: 100 mm
- Projection:
 - 75 mm (rubber absorber)
 - 200 mm (metal extender)
- Material: 2 mm thick, antibacterial PVC and Bs2d0 fire-rated, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: of the aluminium rail onto the rubber absorbers or the metal extenders with metal expansion plugs
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION

- Description: double vertical bedhead protection (Combo'Bedkit as manufactured by SPM) from slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC achieving Bs2d0 fire rating with solid colour. It comprises vertical PVC profile to snap-fix onto aluminium rail with 2 end pieces. It projects 75 mm (on rubber absorbers) or 200 mm (on metal extenders), is 750 mm high and 100 mm wide. These parts fit together on 2 rubber absorbers (25 mm thick) or on 2 metal extenders (150 mm long).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: fixes aluminium rail onto the rubber absorbers or the metal extenders then the end pieces and snap-fixes onto the PVC profile.



Colours available per product:
please see the colour summary hinge

Let discover technical solutions at the end of the guide

Specifications and section drawings on our website www.spm-international.com
BimObject in Revit and Archicad




Contact 350


Contact 200



Contact 350 // 15 colours*



Contact 200 // 31 colours



* and 16 colours on request with a minimum order quantity.

CONTACT

ADHESIVE PROTECTION PLATES

350/200 MM HIGH





APPLICATIONS

Both resistant and decorative, the Contact protection plates prevent damage to doors and walls exposed to furniture and bed scratches, chair frictions and repeated impacts from trolleys (corridors, bedrooms and waiting rooms in public buildings).

It also matches the Impact protection rails.

DESCRIPTION

- Model: Contact 350 or 200 adhesive protection plate
- Height: 350 or 200 mm
- Thickness: 2.5 mm
- Length: 4 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth with decorative grooves
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours:
 - 31 standard for Contact 200
 - 15 standard for Contact 350




SPECIFICATION


- Description: adhesive protection plate (Contact 350 or 200 as manufactured by SPM) from smooth and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile is 350 or 200 mm high and 2.5 mm thick. It provides a smooth surface finish with decorative grooves. A protective film is specified to minimise cleaning before acceptance. It is provided with 2 or 3 strips of double-sided adhesive foam tape for fixing.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/ BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.



Combo'Clad 200



Combo'Clad 150



Combo'Clad 200/150
// 4 colours*



*and 27 colours on request with a minimum order quantity.

COMBO'CLAD

ADHESIVE PROTECTION PLATES - 200/150 MM HIGH



APPLICATIONS

These protection plates prevent damage to doors and walls exposed to scratches by furniture, chairs and to repeated impacts in low traffic corridors, bedrooms, waiting rooms.



Combo'Clad matches the Combo'Punch protection rails.

DESCRIPTION

- Model: Combo'Clad 200 or 150 adhesive⁽¹⁾ protection plate
- Height: 200 or 150 mm
- Thickness: 3 mm
- Length: 4 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

⁽¹⁾ Also available without adhesive tape on request.



SPECIFICATION

- Description: adhesive protection plate (Combo'Clad 200 or 150 as manufactured by SPM) from slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile is 200 or 150 mm high and 3 mm thick. It is provided with 3 strips of double-sided adhesive foam tape for fixing (or without adhesive tape on request).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.



DECOCHOC

PROTECTION AND COVERING PANEL - 2 MM



APPLICATIONS

Wall protection for large surfaces in order to cover all parts exposed to impact. This panel can be used in bedrooms and some corridors (healthcare institutions, schools, etc.) and both in operating theatres or cleanrooms.

The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.

Its finish is subtle and matt for a muted, sober appearance with all the usual levels of resistance to impact, scratches, wear and chemical agents.


DESCRIPTION

- Model: Decochoc protection and covering panel
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 33 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION



- Description: protection and covering panel (Decochoc as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface (Optimixt grain as manufactured by SPM). 3 m long, 1.30 m high, 2 mm thick.
- The level required for biocleaning should be validated for very high infectious risk areas such as operating theatres (*sector 4 according to the Pasteur Institute of Lille France*). The chemical and mark resistance should have been proved on the usual cleaning products according to NF EN ISO 26987. The ease of nuclear decontamination according to DIN 25415 / ISO 8690 should be excellent.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.




FOR AN IMPECCABLE FINISH:

- Fin'Alu: finishing and jointing profiles in satin silver anodised aluminium
- Fin'Color: finishing and jointing profiles in smooth PVC
- Silicone joints
- Welding rods

Colour coordinated with the panels





Decosmic // 3 colours



DECOSMIC

PROTECTION AND COVERING PANEL - 2 MM
METALLIC LOOK



APPLICATIONS

With its slightly grained, matt surface, Decosmic panel protects and decorates the walls and doors in your premises while also meeting hygiene and impact resistance requirements.

The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.


The metallic colours designed by SPM will embellish your spaces in an elegant, on-trend way (restaurant, hotel rooms, reception area, etc.) and bring a unique touch to your establishment.

DESCRIPTION

- Model: Decosmic protection and covering panel - metallic look
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 3 standard

SPECIFICATION



- Description: protection and covering panel, metallic look (Decosmic as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface. 3 m long, 1.30 m high, 2 mm thick.
- The level required for biocleaning should be validated for very high infectious risk areas such as operating theatres (*sector 4 according to the Pasteur Institute of Lille France*). The chemical and mark resistance should have been proved on the usual cleaning products according to NF EN ISO 26987. The ease of nuclear decontamination according to DIN 25415 / ISO 8690 should be excellent.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



FOR AN IMPECCABLE FINISH:

- Fin'Alu: finishing and jointing profiles in satin silver anodised aluminium
- Silicone joints
- Welding rods

Colour coordinated
with the panels




WALL
PROTECTION






Decowood
// 7 wood effect decors



Decotrend
// 4 trend effect decors



DECOWOOD

DECORATIVE PROTECTION AND COVERING PANEL - 2 MM
WOOD EFFECT



APPLICATIONS

This panel has been designed to protect from impacts, scratches and frictions whilst offering protection and warmth of a wood effect finish in retirement homes, clinics, schools, hotels...


The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.

DESCRIPTION


- Model: Decowood decorative protection and covering panel
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: wood effect Bs2d0 fire-rated PVC
- Surface finish: wood effect
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range.
- Colours: 7 standard wood effect decors

SPECIFICATION


- Description: wood effect decorative protection and covering panel (Decowood as manufactured by SPM) from rigid wood effect PVC achieving Bs2d0 fire rating and impact and scratch resistance. A protective film is specified to minimise cleaning before acceptance. 3.00 m long, 1.30 m high, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



PVC wood effect decor
2 mm thick



Welded joint



Welded joint

DECOTREND

DECORATIVE PROTECTION AND COVERING PANEL - 2 MM
TREND EFFECT



APPLICATIONS

This range of panels uplifts and highlights interiors in an original manner and fits into a modern and urban design.

Their high degree of strength is useful for covering walls of bedrooms, reception areas and dining areas in hotels, retirement homes, schools or any form of establishment open to the public.


The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.

DESCRIPTION


- Model: Decotrend decorative protection and covering panel
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: trend decor Bs2d0 fire-rated PVC
- Surface finish: metalized or concrete effect
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 4 standard trend decors

SPECIFICATION


- Description: trend effect decorative protection and covering panel (Decotrend as manufactured by SPM – Composite or Brushed Aluminium or Concrete) from rigid metalized or concrete effect PVC achieving Bs2d0 fire rating and impact and scratch resistance. A protective film is specified to minimise cleaning before acceptance. 3.00 m long, 1.30 m high, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/ BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



PVC trend decor
2 mm thick



Welded joint



Welded joint





Decoclean // 5 colours



DECOCLEAN

SMOOTH PROTECTION AND COVERING PANEL - 2 MM



BACTERICIDAL
on request

APPLICATIONS

This wall protection has been especially developed for areas exposed to a high risk of infection in order to help in the fight against in-hospital illnesses and to reduce bacterial proliferation.

It is recommended for:

- Operating theatres,
- Intensive care, transplant and serious burns wards,
- Neonatology,
- Central sterilisation,
- All high infection risk areas, including those at Level 4 on the Pasteur scale.

The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.


DESCRIPTION

- Model: Decoclean smooth protection and covering panel
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 5 standard

SPECIFICATION



- Description: smooth protection and covering panel (Decoclean as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and smooth surface. 3.00 m long, 1.30 m high, 2 mm thick. A protective film is specified to minimise cleaning before acceptance.
- The level required for biocleaning should be validated for very high infectious risk areas such as operating theatres (*sector 4 according to the Pasteur Institute of Lille France*). The chemical and mark resistance should have been proved on the usual cleaning products according to NF EN ISO 26987. The ease of nuclear decontamination according to DIN 25415 / ISO 8690 should be excellent. For installation in areas where the particle contamination have to be mastered, the ISO Class 5 certification is required according the ISO 14644-1 standard.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.

WALL
PROTECTION



FOR AN IMPECCABLE FINISH:

- Silicone joints
 - Welding rods
- Colour coordinated with the panels





// 7 colours on request*

*with a minimum order quantity

DECOCHOC H₂O

PROTECTION AND COVERING PANEL - 1.5 MM
FOR WET AREAS



APPLICATIONS

Panel specially designed to protect walls and doors in wet rooms (bathrooms, toilets, kitchens, etc.). Its finely grained, matt surface provides optimal water repellency and scratch resistance.

The product can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.


The formulation is specifically developed to ensure an optimum fusion of panels and floor coving with the H₂O welding rods matching the profile colours. This system provides total watertightness, approved by the CSTB and certified by a Technical Approval.

DESCRIPTION

- Model: Decochoc H₂O protection and covering panel for wet areas
- Standard dimensions: 2.50 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 1.5 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured. Specific wet area Hydr'X grain
- Fixing: adhesive bonding with SPM acrylic glue. Joints between panels should be made using PVC welding rods, colour matched to the range
- Colours: 5 standard


SPECIFICATION

- Description: protection and covering panel for wet areas (Decochoc H₂O as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour. Its surface is slightly textured with a fine and matte grain finish (Hydr'X grain as manufactured by SPM) perfectly suitable for wet areas due to its water-repellent qualities that limit the development of scale while ensuring optimal scratch resistance. 2.50 m long, 1.30 m high, 1.5 mm thick.
- To ensure watertightness of the system, the panels are thermowelded to each other and to the PVC floor coving by means of a welding rod (H₂O welding rod as manufactured by SPM). Any connections with other materials are made with a silicone joint (H₂O silicone joint as manufactured by SPM). The chemical and mark resistance of the panel should have been proven on the usual cleaning products according to NF EN ISO 26987.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions. The installer must have been trained beforehand by the manufacturer to install this system.



FOR AN IMPECCABLE AND PERFECTLY WATERTIGHT FINISH:

- Welding rods H₂O
 - Silicone joints H₂O
- Colour coordinated with the panels





Decotrend H₂O
// 1 standard decor

0050 Brushed
aluminum

Decotrend H₂O & Decowood H₂O
// 3 decors on request*

0053 Medium
concrete

0007 Brown cedar

0008 Smoky cedar

* with a minimum order quantity

DECOTREND H₂O & DECOWOOD H₂O

DECORATIVE PROTECTION AND COVERING PANEL - 2 MM
FOR WET AREAS



APPLICATIONS

Panels specially designed to protect walls and doors in wet rooms (bathrooms, toilets, kitchens, etc.). Original, design and trendy, they enhance interiors with efficient protection.

They can be thermoformed for use on round pillars (diameter under 800 mm) and to ensure a perfect hygiene in the angles.


Their formulation is specifically developed to ensure an optimum fusion of panels and floor coving with the H₂O welding rod matching the profile colours. This system provides total watertightness, approved by the CSTB and certified by a Technical Approval.

DESCRIPTION

- Model: Decowood H₂O or Decotrend H₂O decorative protection and covering panel for wet areas
- Standard dimensions: 2.50 m x 1.30 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 2 mm
- Material: Bs2d0 fire-rated PVC
- Surface finish:
 - wood effect for Decowood
 - metalized or concrete effect for Decotrend
- Fixing: adhesive bonding with SPM acrylic glue. Joints between panels should be made using PVC welding rods, colour matched to the range
- Colours: 1 standard decor


SPECIFICATION

- Description: decorative protection and covering panel for wet areas (Decotrend H₂O or Decowood H₂O as manufactured by SPM) from rigid and wood or trend decor PVC achieving Bs2d0 fire rating. The surface finish is metalized or concrete, or wood. 2.50 m long, 1.30 m high, 2 mm thick. A protective film is specified to minimise cleaning before acceptance.
- To ensure watertightness of the system, the panels are thermowelded to each other and to the PVC floor coving by means of a welding rod (H₂O welding rod as manufactured by SPM). Any connections with other materials are made with a silicone joint (H₂O silicone joint as manufactured by SPM). The chemical and mark resistance of the panel should have been proven on the usual cleaning products according to NF EN ISO 26987.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions. The installer must have been trained beforehand by the manufacturer to install this system.




FOR AN IMPECCABLE AND PERFECTLY WATERTIGHT FINISH:

- Welding rods H₂O
 - Silicone joints H₂O
- Colour coordinated with the panels





Decochoc Staro // 9 colours



DECOCHOC STARO

PROTECTION AND COVERING PANEL - 1.5 MM



APPLICATIONS

Decochoc Staro, the new SPM protection and covering panel, is a PVC-free solution.

With solid colour and finely textured matt surface finish, Decochoc Staro offers a wide range of applications that allows you a great deal of freedom when designing your layouts.

Resistant to chemical substances, this panel guarantees a complete watertightness.

With Decochoc Staro, SPM is providing a solution designed to meet the vital requirements of the healthcare and education sectors. One of the main characteristics of the product lies in its compatibility with the extremely stringent requirements of fire reaction class Bs1d0.

With a long lifecycle, it respects the environment and the vital need for sustainability.


The range comprises nine modern colours.

DESCRIPTION

- Model: Decochoc Staro protection and covering panel
- Standard dimensions: 3 m x 1.25 m
- Custom options: cutting to size, bend into L/U, thermoforming, chamfer
- Thickness: 1.5 mm
- Material: Bs1d0 fire-rated PVC-free (Staro), solid colour
- Surface finish: matt and slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints, colour matched to the range
- Colours: 9 standard

SPECIFICATION



- Description: protection and covering panel (Decochoc Staro as manufactured by SPM) from rigid PVC-free (Staro) achieving Bs1d0 fire rating with solid colour and slightly textured matt surface. 3 m long, 1.25 m high, 1.5 mm thick.
- The level required for biocleaning should be validated for very high infectious risk areas such as operating theatres (*sector 4 according to the Pasteur Institute of Lille France*). The chemical and mark resistance should have been proved on the usual cleaning products according to NF EN ISO 26987, ASTM D543 and ASTM D1308.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



FOR AN IMPECCABLE FINISH:

- Fin'Alu: finishing and jointing profiles in satin silver anodised aluminium
- Fin'Color: finishing and jointing profiles in smooth PVC
- Silicone joints

Colour coordinated with the panels



WALL PROTECTION





Fin'Alu // 1 colour

Satin silver
anodised



Fin'Color // 33 colours



FIN'ALU


FINISHING AND JOINTING PROFILES FOR 2 MM PANELS
DECOCHOC, DECOSMIC, DECOWOOD AND DECOTREND PANELS

APPLICATIONS

Fin'Alu profiles are designed to finish or joint Decochoc, Decosmic, Decowood and Decotrend protection panels and to bring a decorative and up-market original touch. They provide a perfect finish in low-traffic corridors, waiting rooms or bedrooms. They fit into healthcare facilities (hospitals, clinics, retirement homes) as well as hotels and service sector.

DESCRIPTION


- Model: Fin'Alu finishing (J shape) or jointing (H shape) profile for 2 mm thick panels
- Width (covering):
 - 18 mm (37.5 mm hidden part) for finishing profile;
 - 42 mm (55 mm hidden part) for joint profile
- Length: 3 m
- Material: satin silver anodised aluminium
- Surface finish: smooth
- Fixing: adhesive bonding with SPM acrylic glue or screwing to wall
- Colour: satin silver anodised




SPECIFICATION

- Description: jointing profile (H shape) in satin silver anodised aluminium (Fin'Alu jointing profile in H shape as manufactured by SPM) designed for vertical or horizontal jointing between 2 mm thick protection panels (Decochoc, Decosmic, Decowood or Decotrend as manufactured by SPM). Smooth surface. The profile, 3 m long and 42 mm wide (visible part), glues onto the continuous aluminium rail, 55 mm wide (hidden part), fixed to the wall by gluing or screwing.
 - Colour: selected by architects from manufacturer's standard range.
 - Installation method: gluing onto aluminium rail to glue or screw to wall as per manufacturer's instructions.
- Description: finishing profile (J shape) in satin silver anodised aluminium (Fin'Alu finishing profile in J shape as manufactured by SPM) designed for vertical or horizontal finishing for 2 mm thick protection panels (Decochoc, Decosmic, Decowood or Decotrend as manufactured by SPM). Smooth surface, 3 m long, 18 mm wide for the visible part and 37.5 mm for the hidden part fixed to the wall.
 - Colour: selected by architects from manufacturer's standard range.
 - Installation method: glue as per manufacturer's instructions or screwing to wall.

1. JOINTING PROFILE (INTO H SHAPE)



2. FINISHING PROFILE (INTO J SHAPE)



FIN'COLOR

FINISHING AND JOINTING PROFILES FOR 2 MM PANELS
DECOCHOC, DECOCLEAN, DECOWOOD AND DECOTREND PANELS



APPLICATIONS


Fin'Color are PVC profiles that provide an aesthetic finish and a perfect joint between panels or between panel and flexible floor covering.

Available in all colours in the range, to be matched with our protection panels, they bring a subtle decorative touch for a harmonious whole.

They are suitable for low traffic areas, enhancing all types of public buildings.


DESCRIPTION

- Model: Fin'Color finishing (J shape) or jointing (H shape) profile for 2 mm thick panels
- Width (visible part):
 - 20.5 mm for finishing profile
 - 21.5 mm for jointing profile
- Length: 3 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours: 33 standard




SPECIFICATION


- Description: jointing profile (H shape) from antibacterial PVC achieving Bs2d0 fire rating with solid colour (Fin'Color jointing profile in H shape as manufactured by SPM) designed for horizontal or vertical jointing between 2 mm thick protection panels (Decochoc, Decoclean, Decowood or Decotrend as manufactured by SPM) or the connection of these panels with 2 mm flexible floor covering. Smooth surface, 3 m long, 21.5 mm wide for the visible part.
 - Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
 - Colour: selected by architects from manufacturer's standard range.
 - Installation method: glue as per manufacturer's instructions.
- Description: finishing profile (J shape) from antibacterial PVC achieving Bs2d0 fire rating with solid colour (Fin'Color finishing profile in J shape as manufactured by SPM) designed for horizontal or vertical finishing for 2 mm thick protection panels (Decochoc, Decoclean, Decowood or Decotrend as manufactured by SPM). Smooth surface, 3 m long, 20.5 mm wide for the visible part.
 - Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
 - Colour: selected by architects from manufacturer's standard range.
 - Installation method: glue as per manufacturer's instructions.



1. JOINTING PROFILE (INTO H SHAPE)




2. FINISHING PROFILE (INTO J SHAPE)






Decofresc - All public contemporary frescoes // 33 colours



Decofresc - Early Childhood frescoes // 3 themes



DECOFRESC

DECORATIVE PROTECTION FRESCO - 2 MM

ALL PUBLIC CONTEMPORARY



APPLICATIONS

The contemporary Decofresc decorative frescoes provide an attractive setting in public buildings.

They bring a touch of elegance and customization while protecting walls and they meet hygiene and impact resistance requirements.


DESCRIPTION

- Model: all public contemporary Decofresc decorative protection fresco
- Standard dimensions: 3 m x 1.30 m indivisible
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 33 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.


SPECIFICATION

- Description: decorative protection fresco (Cloud or Wave Decofresc as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface (Optimixt grain as manufactured by SPM). 3 m long, 1.30 m high (indivisible), 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



NOTA

Frescoes made from cut-to-size Decochoc panels (p.64-65).



Wave



Cloud

DECOFRESC

DECORATIVE PROTECTION FRESCO - 2 MM

EARLY CHILDHOOD



APPLICATIONS

The Early Childhood Decofresc decorative frescoes are especially designed to brighten up and durably protect walls in establishments who hope to create an attractive, welcoming atmosphere that stimulates children's imagination. They meet the constraints linked to the early childhood: hygiene and impact resistance.

DESCRIPTION

- Model: Early Childhood Decofresc decorative protection fresco
- Standard dimensions: 3 m x 1.30 m indivisible
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints or PVC welding rods, colour matched to the range
- Colours: 3 themes each with 4 pictures (in predefined colours)

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

NOTA

Frescoes made from cut-to-size Decochoc panels (p. 64-65).

Delivered flat and pre-assembled, they are to bring together when installing and not fit on curved walls.




Altitude theme (4 pictures)



Savannah theme (4 pictures)



Maritime theme (4 pictures)



Maritime theme picture n°1

Colours available per product: please see the colour summary hinge

Let discover technical solutions at the end of the guide

Specifications and section drawings on our website www.spm-international.com BimObject in Revit and Archicad



RELEASE THE CREATIVITY OF YOUR WALLS !

The perfect combination to decorate and customize your interior.

More than a panel which covers your walls, Decoprint combines your inspiration and aesthetic ideal to your compelling need to preserve your interior.

Decoprint enhances your walls, your doors, and offers a touch of elegance in your establishment. Decoprint comes to infinity in any living space.

Let your creativity flow, we realize your custom-made project.

DECOPRINT

DECORATIVE PANEL - 1 MM

WITH CUSTOMIZED DIGITAL PRINTING

APPLICATIONS

The Decoprint printed panel is the original solution created and developed by SPM. We custom-build your decoration panel, using digital printing to place your image (photograph, drawing, logo, text, etc.) on the back of the panel, in the requested size. It is also possible to link images to provide a continuous image.

It enhances a touch of elegance and originality in buildings looking for aesthetic or signage solutions to cover walls in form.

The Decoprint panel creates a welcoming environment while meeting the hygiene requirements necessary in buildings that are open to the public.


DESCRIPTION

- Model: Decoprint decoration panel with customized digital printing
- Height: made-to-measure (maximum 1.20 m)
- Width: made-to-measure (maximum 2.90 m)
- Thickness: 1 mm
- Material: translucent PVC-free with image printed on the back
- Surface finish: matt and smooth
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant. Joints between panels can be made using silicone joints, colour matched to the range.
- Colours: translucent for customization.

SPECIFICATION

- Description: decorative panel with customized digital printing (Decoprint as manufactured by SPM). Translucent and rigid PVC-free with images printed on the back, its surface is matt and smooth. Its maximum height is 1.20 m and its maximum length is 2.90 m and is 1 mm thick. A protective film is specified to minimise cleaning before acceptance.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: customized and selected by architects*
- Installation: glue as per manufacturer's instructions.




* The reproduced images or photos, provided by the user in accordance with SPM requested specification, must be free of copyright – if they are not, the reproduction rights are payable by the user, who has full responsibility.



NOTA


The reproduced images or photos, provided by the user in accordance with SPM requested specification, must be free of copyright – if they are not, the reproduction rights are payable by the user, who has full responsibility.

SPM CARRIES OUT YOUR CUSTOMIZED PANEL!



Call our local service for answers to all your questions and to create a customized panel.

WALL
PROTECTION



DECOCARE HAND HYGIENE PANEL - 1 MM



APPLICATIONS

Decocare hand hygiene panel combines a public health message with effective protection of the walls above sinks. The educational pictograms are easy to understand and encourage good hand hygiene in order to limit the spread of hand-borne germs.

The panel provides decorative wall protection and can be installed in all wet rooms to spell out the hand washing routine.

It can also be customized with your logo or other text.


DESCRIPTION

- Model: Decocare hand hygiene panel
- Dimensions:
 - Classic: 600 x 400 mm
 - Fountain: 600 x 600 mm
 - Made-to-measure
- Thickness: 1 mm
- Material: translucent PVC-free with visual printed on the back
- Surface finish: matt and smooth
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours: 2 standard models
- Option: customization


SPECIFICATION

- Description: hand hygiene panel, classic or fountain shape (Decocare as manufactured by SPM). Translucent and rigid PVC-free with a visual printed on the back, its surface is matt and smooth. Its width is 600 mm, its height is 400 mm (classic) or 600 mm (fountain) and its thickness is 1 mm. A protective film is specified to minimise cleaning before acceptance.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range. Customized on request.
- Installation method: glue, as per manufacturer's instructions.

CUSTOMIZING ON REQUEST



Decocare Fountain



Decocare Classic

DECOKID EDUCATIONAL PANEL - 1 MM



APPLICATIONS

SPM's educational panels Decokid bring to life a number of messages in bright colours, aimed at children, whilst still providing wall protection. Putting across educational principles to small children by means of immediately understandable images within their school environment is an effective educational aid.

Hygiene, environment, safety, etc., SPM's educational panels illustrate real situations that relate to children's daily lives.

DESCRIPTION

- Model: Decokid Educational panel
- Standard dimensions: 750 x 1300 mm
- Thickness: 1 mm
- Material: translucent PVC-free with visual printed on the back
- Surface finish: matt and smooth
- Fixing: adhesive bonding with SPM acrylic glue or with SPM multipurpose adhesive sealant
- Colours: 11 designs available (in predefined colours)

SPECIFICATION

- Description: educational panel (Decokid as manufactured by SPM). Translucent and rigid PVC-free with a visual printed on the back, its surface is matt and smooth. Its width is 750 mm, height 1300 mm and thickness 1 mm. A protective film is specified to minimise cleaning before acceptance.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue, as per manufacturer's instructions.



1. I cross the road at a pedestrian crossing.

EDUCATIONAL PANELS: A UNIQUE AND ORIGINAL CONCEPT

- Matched to all existing colour schemes
- Extends a building's working life
- Resists damage from even the harshest cleaning materials
- Easy to install



2. Early to bed, early to rise.



3. 30 mph, that's the urban speed limit.



4. I always say, 'Hello'.



5. I always put my rubbish in the bins provided.



6. I always wash my hands before eating.



7. I always wear my seat belt in the car.




8. I take breaks from my video games.




9. I always wash my hands after using the toilet.



10. No pushing.



11. I never leave the tap running.



Colours are not contractually binding.





For further information about installation of SPM accessories and use of glues, silicone joints and welding rods, please consult our Installation Procedure Guide.

PLAC'INOX

BRUSHED STAINLESS STEEL PROTECTION PLATE - 10/10th



APPLICATIONS

Plac'Inox protection plate reinforces those areas subject to impacts and is approved for food-handling areas (304L).


Suitable for use in areas of heavy use or wet places, they are particularly useful in the food and pharmaceutical industries as well as in healthcare establishments, central kitchens, etc.

DESCRIPTION

- Model: Plac'Inox protection plate
- Height: as required (1.25 m maxi)
- Length: as required (2.50 m maxi)
- Thickness: 10/10th
- Material: stainless steel (304L approved for food handling areas)
- Fixing: adhesive bonding with SPM multipurpose adhesive sealant
- Finish: brushed metal

SPECIFICATION

- Description: protection plate (Plac'Inox as manufactured by SPM) 10/10th thick in brushed stainless steel 304L approved for food handling areas. Its maximum length is 2.50 m and its maximum height 1.25 m. A protective film is specified to minimise cleaning before acceptance.
- Finish: brushed metal.
- Installation method: glue as per manufacturer's instructions.



SOLUTIONS FOR PANELS

FIXING



SPM universal primer
(100 to 150 g required per m²)
5 l drum



SPM acrylic glue - Simple bonding
Solvent-free
(300 to 350 g required per m²) - Available in 6 or 14 kg jars



SPM multipurpose adhesive sealant
Solvent-free
290 ml cartridge (about 25 ml of cord)



Double-sided foam adhesive roll 4957/15 mm wide
(contact us prior to use)
25 m roll



Double-sided adhesive roll 4970/50 mm wide
For installation on doors or laminates
(contact us prior to use) - 50 m roll



Silicone joint for Decochoc, Decosmic, Decowood, Decotrend, Decoclean, and Decochoc H₂O panels (matching colours)
310 ml cartridge



Welding rod for Decochoc, Decowood, Decotrend, Decoclean and Decochoc H₂O panels (matching colours)
100 m roll


FINISHING AND JOINTING PROFILES



Fin'Color
Finishing and jointing profiles for Decochoc, Decoclean, Decowood and Decotrend panels
Antibacterial PVC*
L. 3.00 m
(See p. 79)



Fin'Alu
Finishing and jointing profiles for Decochoc, Decosmic, Decowood and Decotrend panels
Satin silver anodized aluminium
L. 3.00 m
(See p. 78)



Fin'Angle
Internal angle jointing profile with mounting base for Decochoc, Decochoc H₂O panels
Antibacterial PVC* (white base)
L. 3.00 m

*Colours available per product: please see the colour summary hinge.



CORNER PROTECTION

Corners are particularly prone to damage so they need to be well protected.

SPM has developed a complete range of carefully designed corner protectors which combat wear and provide effective, safe protection. The corner protectors are either adhesive, for corners exposed to light impact, or on aluminium core, for corners in areas with intense activity, whether 90° or not.

All have the same properties: they resist impact and effects of cleaning and disinfectant products, and have a Bs2d0 fire rating.



CORNEA



CORNEA



COMBO' CORNER



PROFILA



SOLUTIONS



PROTECTA 2



PROFILA



CORNEAFLEX

CORNER PROTECTION

ON ALUMINIUM CORE

ADHESIVE



CORNEA p.92
90° corner protector
with strip on core



CORNEAFLEX p.93
135° and variable angle corner
protector with flexible strip on
core



COMBO'CORNER p.94
90° corner protectors
on core



COMBO'CORNER p.95
135° angle corner
protector on core



LINEA'FLEX p.96
Flexible adhesive corner protector
with variable angle endcap



PROTECTA 2 p.97
Variable angle flexible adhesive
corner protector



COMBO'FLEX p.98
Variable angle flexible adhesive
corner protector



COMBO'LINE p.99
90° adhesive
corner protectors



PROFILA p.100
90° adhesive
corner protectors




PROFIL'INOX p.101
Adhesive 90° corner protectors
in brushed stainless steel

	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
CORNEA		90° corner protector with strip on core	PVC + aluminium	31 colours
CORNEAFLEX		135° and variable angle corner protector with flexible strip on core	PVC + aluminium	5 colours
COMBO'CORNER		90° and 135° angle corner protectors on core	PVC + aluminium	32 colours

	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
LINEA'FLEX		80° to 115° adhesive corner protector with variable angle endcap	PVC	33 colours
PROTECTA 2		50° to 155° adhesive corner protector	PVC	33 colours
COMBO'FLEX		50° to 155° adhesive corner protector	PVC	4 colours
COMBO'LINE		90° adhesive corner protectors	PVC	33 colours
PROFILA		90° adhesive corner protectors	PVC	33 colours
PROFIL'INOX		90° adhesive corner protectors	Stainless steel	Brushed finish



Cornea // 31 colours



Corneaflex // 5 colours*



*and 26 colours on request with a minimum order quantity.

CORNEA

90° CORNER PROTECTOR WITH STRIP ON CORE



APPLICATIONS

Efficient protection for 90° angles exposed to heavy impact from trolleys and carts. A unique rounded edge makes corners harmless.



Recommended for corridors and entrances to hospitals, clinics, laboratories, central kitchens, schools.

DESCRIPTION

- Model: Cornea corner protector with strip on core
- Angle: 90°
- Wing width: 60 mm (internal measurement)
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, 2.5 mm thick
- Surface finish: smooth
- Fixing system: continuous pre-drilled aluminium core
- Colours: 31 standard

SPECIFICATION

- Description: 90° corner protector with strip on core (Cornea as manufactured by SPM) from smooth and antibacterial PVC, 2.5 mm thick, achieving Bs2d0 fire rating with solid colour. Wings are 60 mm wide (internal measurement) and snap-fix onto a continuous pre-drilled aluminium core. Its rounded edge forms a decorative and harmless strip. A protective film is specified to minimise cleaning before acceptance. The corner protector is finished with a smooth PVC endcap.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: snap-fixes onto continuous pre-drilled aluminium core screwed to the wall.



Colours available per product:
please see the colour summary hinge

CORNEAFLEX

135° AND VARIABLE ANGLE CORNER PROTECTOR WITH FLEXIBLE STRIP ON CORE





APPLICATIONS

High-performance protection for corners: 135° or variable angles. Designed with an impact-resistant flexible edge and flexible PVC reinforcement beads, this product makes corners safe and protects them against heavy traffic.

For use in corridors and entrances to kitchens, laboratories, hospitals, clinics and schools.

DESCRIPTION

- Model: Corneaflex corner protector with flexible strip on core
- Angle: 135° or variable angle from 80° to 135°
- Wing width: 65 mm (internal measurement)
- Length:
 - 1.30 m, 2.00 m or 4.00 m (135°)
 - 4.00 m (variable angle)
- Material: antibacterial PVC, solid colour combining
 - rigid wings Bs2d0 fire-rated, 2.5 mm thick
 - a flexible strip, 3.5 mm thick
- Surface finish: smooth
- Fixing system: continuous pre-drilled aluminium core for 135° angle. The core is in two parts for variable angles
- Colours: 5 standard



* Only for 135° angle

Colours available per product:
please see the colour summary hinge

Specifications and section drawings on our website www.spm-international.com
BimObject in Revit and Archicad

Let discover technical solutions at the end of the guide





Combo'Corner 75 and 50 // 4 colours*



*and 28 colours on request with a minimum order quantity.



Combo'Corner 135 // 4 colours*



*and 28 colours on request with a minimum order quantity.

COMBO'CORNER 75 AND 50

90° CORNER PROTECTORS ON CORE



APPLICATIONS

Combo'Corner 75 or 50 protects the 90° corners in corridors from heavy traffic of equipments.



DESCRIPTION

- Model: Combo'Corner 75 or 50 corner protector on core
- Angle: 90°
- Wing width (internal measurement):
 - 68 mm Combo'Corner 75
 - 46 mm Combo'Corner 50
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, 2 mm thick
- Surface finish: smooth or slightly textured ("Optimixt" grain*)
- Fixing: continuous aluminium core
- Colours: 4 standard

*"Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION

- Description: 90° corner protector on core (Combo'Corner 75 or 50 as manufactured by SPM) from smooth or slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC, 2 mm thick, achieving Bs2d0 fire rating with solid colour. Wings are 68 mm or 46 mm wide (internal measurement) and snap-fix onto a continuous aluminium core. The corner protector is finished with a slightly textured PVC endcap.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: snap-fixes onto continuous aluminium core screwed to the wall.



COMBO'CORNER

135° CORNER PROTECTOR ON CORE



APPLICATIONS

This corner protector prevents high impact damage from wheeled traffic for 135° angles in corridors thanks to its shock absorbent PVC on continuous aluminium core.



DESCRIPTION


- Model: Combo'Corner corner protector on core
- Angle: 135°
- Wing width: 68 mm (internal measurement)
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, 2 mm thick
- Surface finish: smooth or slightly textured ("Optimixt" grain*)
- Fixing: continuous aluminium core
- Colours: 4 standard

*"Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION

- Description: 135° corner protector on core (Combo'Corner as manufactured by SPM) from smooth or slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC, 2 mm thick, achieving Bs2d0 fire rating with solid colour. Wings are 68 mm wide (internal measurement) and snap-fix onto a continuous aluminium core. The corner protector is finished with a slightly textured PVC endcap.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: snap-fixes onto continuous aluminium core screwed to the wall.





LINEA'FLEX

FLEXIBLE ADHESIVE CORNER PROTECTOR WITH VARIABLE ANGLE ENDCAP



APPLICATIONS

The Linea'Flex corner protector is the product of advanced technical expertise, combining impact resistance, flexibility and discretion, and blending perfectly with the Linea range. It provides effective protection for all angles from 80° to 115° thanks to its flexible central part mounted on two dampers for added resistance.


Thanks to its variable angle endcap it fits to any height with maximum hygiene.

Installation is quick and easy with two strips of double-sided adhesive tape.

It blends discreetly into corridors and rooms that are exposed to repeated impacts in hospitals, clinics, retirement homes, schools, hotels, restaurants, offices and stores.

DESCRIPTION

- Model: Linea'Flex flexible adhesive corner protector with variable angle endcap
- Angle: from 80° to 115°
- Wing width: 45 mm (internal measurement)
- Thickness: cross-section up to 3 mm
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 33 standard



PROTECTA 2

VARIABLE ANGLE FLEXIBLE ADHESIVE CORNER PROTECTOR




APPLICATIONS

Thanks to its rounded, reinforced flexible strip, this product provides efficient, decorative and economical protection for all corners exposed to frequent impact.

Available in 33 standard colours, this model blends in with all interior decoration styles in public buildings.


DESCRIPTION

- Model: Protecta 2 flexible adhesive corner protector
- Angle: from 50° to 155°
- Wing width: 60 mm (internal measurement)
- Thickness: 2 mm
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 33 standard





Combo'Flex // 4 colours



Combo'Line 75 / 50 / 25 // 4 colours*



*and 29 colours on request with a minimum order quantity

COMBO'FLEX

VARIABLE ANGLE FLEXIBLE ADHESIVE CORNER PROTECTOR



APPLICATIONS

Combo'Flex protects all corners exposed to frequent and light impact in hotels, schools, offices or nurseries.

Its matte finish is provided by its slightly textured surface.



DESCRIPTION

- Model: Combo'Flex flexible adhesive^[1] corner protector
- Angle: from 50° to 155°
- Wing width: 60 mm (internal measurement)
- Thickness: 2 mm
- Length: 1.30 m, 2.00 m or 4.0m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.

SPECIFICATION

- Description: variable angle adhesive corner protector (from 50° to 155°) with flexible strip (Combo'Flex as manufactured by SPM) from slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC, 2 mm thick, achieving Bs2d0 fire rating with solid colour. Wings are 60 mm wide (internal measurement). It is provided with 2 strips of double-sided adhesive foam tape for fixing (or without adhesive tape on request).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.



^[1] Also available without adhesive tape on request.

Colours available per product:
please see the colour summary hinge

Let discover technical solutions at the end of the guide

COMBO'LINE 75, 50 AND 25

90° ADHESIVE CORNER PROTECTORS



APPLICATIONS



These corner protectors blend in seamlessly with all interiors and protect corners from light impact. The slightly textured surface gives them a matte finish.

Combo'Line 25 suits also for door frame protection.

DESCRIPTION

- Model: Combo'Line 75, 50 or 25 adhesive^[1] corner protectors
- Angle: 90°
- Wing width (internal measurement):
 - 75 mm Combo'Line 75
 - 50 mm Combo'Line 50
 - 25 mm Combo'Line 25
- Thickness: 2 mm
- Length: 1.30 m, 2.00 m or 4.0m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.




^[1] Also available without adhesive tape on request.

Colours available per product:
please see the colour summary hinge

Let discover technical solutions at the end of the guide





Profil'Inox
// Brushed finish

PROFILA 50 AND 30

90° ADHESIVE CORNER PROTECTORS



APPLICATIONS

These corners protectors blend in seamlessly with all interiors and protects corners from light impacts.

Profila 30 can also protect some door frames.

DESCRIPTION

- Model: Profila 50 or 30 adhesive corner protector
- Angle: 90°
- Wing width (internal measurement):
 - 50 mm Profila 50
 - 30 mm Profila 30
- Thickness: 2 mm
- Length: 1.30 m, 2.00 m or 4.00 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours: 33 standard

SPECIFICATION

- Description: 90° adhesive corner protector (Profila 50 or 30 as manufactured by SPM) from smooth and antibacterial PVC, 2 mm thick, achieving Bs2d0 fire rating with solid colour. Wings are 50 or 30 mm wide (internal measurement). A protective film is specified to minimise cleaning before acceptance. It is provided with 2 strips of double-sided adhesive foam tape for fixing.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.

PROFIL'INOX 50 AND 30

90° ADHESIVE CORNER PROTECTORS IN BRUSHED STAINLESS STEEL



APPLICATIONS

Profil'Inox protect 90° corners exposed to impacts. They are instantly recognisable by their rounded edge and lightly beveled sides.

They are approved for use in food-handling areas.







Ideally suited for heavily used or wet areas, they are particularly useful in the food and pharmaceutical industries as well as in healthcare establishments, central kitchens, etc.

DESCRIPTION

- Model: Profil'Inox 50 or 30 adhesive corner protector
- Angle: 90°
- Wing width: 50 or 30 mm (internal measurement)
- Thickness: 10/10th
- Length: 2.50 m
- Material: 304L stainless steel (approved for food-handling areas)
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Finish: brushed metal

SPECIFICATION

- Description: 90° adhesive corner protector with 50 or 30 mm wings (internal measurement) (Profil'Inox 50 or 30 as manufactured by SPM), 10/10th thick in 304L brushed stainless steel approved for food handling areas and provided with two strips of double-sided adhesive foam tape.
- Wings are lightly beveled. A protective film is specified to minimise cleaning before acceptance.
- Finish: brushed metal.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.



DOOR PROTECTION

In health and other public building establishments, doors are subjected to the harshest of tests: the faces and edges are particularly exposed and prone to damage, and are crashed by trolleys, stretchers and other mobile equipment.


SPM has developed a range of protection panels and hand-plates.

Cut-to-size, bended into L or U bends, they fit all types of woodwork.

It is essential to protect and you can also add a decorative touch with some of SPM's original cutouts.




FOOT-HEIGHT DOOR



HANDPLATES



HALF-HEIGHT DOOR



BENDS INTO U AND L SHAPE



INLAID SIGNAGE



INLAID SIGNAGE



HALF-HEIGHT DECORATIVE DOOR - TWO-COLOUR



HANDPLATES



FOOT-HEIGHT DOOR p.106
Contact plates
Plac’Inox



HALF-HEIGHT DOOR p.107
Decochoc panel
Decosmic panel
Plac’Inox
- straight cut -



HALF-HEIGHT DECORATIVE DOOR..... p.108-109
Decochoc panel
Decosmic panel
(one or two-colour)
- decorative cutouts -



HANDPLATES p.110
Decochoc panel
Decosmic panel
- decorative cutouts -



HALF-HEIGHT DOOR INLAID SIGNAGE p.111
Numerals, pictos
and early childhood



EDGES AND FRAMES p.112-113
Decochoc panel
Decosmic panel
- bends and thermoforming -

	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
FOOT-HEIGHT DOOR		Contact 350 or 200 plates	PVC	15 or 31 colours
HALF-HEIGHT DOOR		Straight cut Decochoc panel	PVC	33 colours
		Straight cut Decosmic panel	PVC	3 colours
		Plac’Inox protection plate	Stainless steel	Brushed finish
HALF-HEIGHT DECORATIVE DOOR		Decochoc panel with decorative cutouts	PVC	33 colours to combine
		Decosmic panel with decorative cutouts	PVC	3 colours to combine
HANDPLATES		Decochoc panel with decorative cutouts	PVC	33 colours
		Decosmic panel with decorative cutouts	PVC	3 colours
INLAID SIGNAGE		Decochoc panel ½ height door	PVC	33 colours for numerals and pictos 11 drawings Early Childhood
		Decosmic panel ½ height door	PVC	3 colours for numerals and pictos
EDGES AND FRAMES		Decochoc panel bends and thermoforming	PVC	33 colours
		Decosmic panel bends and thermoforming	PVC	3 colours



* and 16 colours with minimum order quantity.

FOOT-HEIGHT DOOR

ADHESIVE PROTECTION PLATES

CONTACT



DESCRIPTION


- Model: Contact 350 or 200 adhesive protection plate
- Height: 350 or 200 mm
- Thickness: 2.5 mm
- Length: 4 m
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: smooth with decorative grooves
- Fixing: adhesive foam tapes to reinforce with SPM multipurpose adhesive sealant
- Colours:
 - 31 standard for Contact 200
 - 15 standard for Contact 350

SPECIFICATION

- Description: adhesive protection plate (Contact 350 or 200 as manufactured by SPM) from smooth and antibacterial PVC achieving Bs2d0 fire rating with solid colour. PVC profile is 350 or 200 mm high and 2.5 mm thick. It provides a smooth surface finish with decorative grooves. A protective film is specified to minimise cleaning before acceptance. It is provided with 2 or 3 strips of double-sided adhesive foam tape for fixing.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive. SPM multipurpose adhesive sealant is recommended for stronger fixing.



Recommended protection height: 200 mm or 350 mm



PLAC'INOX STAINLESS STEEL PROTECTION PLATE

Please refer to page 86



HALF-HEIGHT DOOR

PROTECTION AND COVERING PANELS - 2 MM

DECOCHOC / DECOSMIC - STRAIGHT CUT -



APPLICATIONS

Protects and decorates doors in corridors and entrances to hospitals, clinics, retirement homes, schools, kitchens, restaurants, collective housing...

To avoid the handle and lock and facilitate installation, we recommend a protection height below either 900 mm or 1100 mm.

DESCRIPTION


- Model: cut-to-size Decochoc or Decosmic protection and covering panel
- Standard dimensions: 3 m x 1.30 m
- Custom options: cutting-to-size, chamfer
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic

SPECIFICATION

- Description: protection and covering panel (Decochoc or Decosmic as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.




Recommended protection height: from 800 mm to 1300 mm



PLAC'INOX STAINLESS STEEL PROTECTION PLATE

Please refer to page 86






Decosmic // 3 colours



Decochoc // 33 colours



HALF-HEIGHT DECORATIVE DOOR

PROTECTION AND COVERING PANELS - 2 MM
DECOCHOC / DECOSMIC - *DECORATIVE CUTOUTS* -

ONE COLOUR

APPLICATIONS

These cutouts provide half-height protection and decoration for doors.

Ideal for use in corridors in public buildings: hospitals, schools, restaurants, hotels...


Shapes and colours make easier the location of different doors: rooms, staff rooms, technical premises, etc.

DESCRIPTION


- Description: one colour protection and covering masks with cut-to-size Decochoc or Decosmic panel
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic

SPECIFICATION


- Description: half-height decorative one colour door protection (Iron, Wave, Mountain or Cubic masks as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.




Iron



Wave



Mountain



Cubic




TWO-COLOUR

APPLICATIONS


These half-door claddings protect and bring a touch of originality. This two-colour range provides visual help by using floor, department, service or section colour schemes, very useful in accessibility process.

DESCRIPTION


- Model: two-colour protection and covering masks with cut-to-size Decochoc or Decosmic panel
- Height: 1200 mm
- Width: 930 or 1230 mm
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic




Stratum




Cubic



Comma



Stairs




Rainbow



SPECIFICATION

- Description: half-height decorative two-colour door protection (Stratum, Cubic, Comma, Stairs, Rainbow masks as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface. Width 930 or 1230 mm, height 1200 mm, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architect from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.





Decochoc
// 33 colours



Decosmic
// 3 colours



Decochoc
// 33 colours



Decosmic
// 3 colours


HANDPLATES

PROTECTION AND COVERING PANELS - 2 MM
DECOCHOC / DECOSMIC - *DECORATIVE CUTOUTS* -



APPLICATIONS

These original shapes are used to decorate and protect doors from wear and dirt around handles.
Perfect for all collective institutions: schools, hotels, offices, restaurants, hospitals, retirement homes...







DESCRIPTION

- Model: mask of handplate with cut-to-size Decochoc or Decosmic panel
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive or SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic

SPECIFICATION

- Description: handplates (Nö, Glass, Lady, Man, Wooden, Dan, Eclipse, Plac'net or Delta masks as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive or glue as per manufacturer's instructions.



INLAID SIGNAGE

FOR HALF-HEIGHT DOOR PROTECTION - 2 MM
IN DECOCHOC OR DECOSMIC




APPLICATIONS

The inlaid signage with numerals, pictos or Early Childhood drawings individually identify your half-door protections in Decochoc or Decosmic by forming an effective and robust marking that is visible from a distance and easy to clean.

The drawings will be highly appreciated by the young public in particular, who will easily be able to find directions.


DESCRIPTION

- Model: Decochoc or Decosmic inlaid signage with Numerals, Pictos or Early Childhood drawings
- Height: 400 mm
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - for the numerals and pictos: 33 standard in Decochoc 3 standard in Decosmic
 - for the Early Childhood drawings: 11 standard drawings (defined colours)




Signage Pictos*

* Other pictos: consult us




Signage Early Childhood drawings





Decosmic // 3 colours



Decochoc // 33 colours



EDGES AND FRAMES

BENDS INTO L AND U SHAPES OF PROTECTION AND COVERING PANELS - 2 MM
DECOCHOC / DECOSMIC

APPLICATIONS

Provides protection for door edges and simple frames edges against frequent impact from trolleys (corridors and entrances to healthcare facilities, laboratories...).


Lateral edges are exposed to impacts from trolleys, beds... and below edges to water leaks in the door. U-bend is perfect for wet rooms such as bathrooms, sanitary arrangements, central kitchens...

DESCRIPTION

- Model: cut-to-size Decochoc or Decosmic* protection and covering panel with bends into L and U shapes
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic

SPECIFICATION

- Description: door protection and covering panel with bends into L or U for edge or frame protection (Decochoc or Decosmic as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface, 2 mm thick.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/ BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: glue as per manufacturer's instructions.



THERMOFORMING OF PROTECTION AND COVERING PANELS - 2 MM DECOCHOC AND DECOSMIC*

APPLICATIONS


For complex door frames which cannot be protected by L or U bends (corridors in hospitals, clinics, nursing homes...).

DESCRIPTION

- Model: cut-to-size Decochoc or Decosmic* protection and covering panel with thermoforming according to template provided
- Thickness: 2 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour
- Surface finish: slightly textured
- Fixing: adhesive bonding with SPM acrylic glue or SPM multipurpose adhesive sealant
- Colours:
 - 33 standard for Decochoc
 - 3 standard for Decosmic

SPECIFICATION

- Description: cut-to-size and thermoformed protection and covering panel (Decochoc or Decosmic as manufactured by SPM) from rigid and antibacterial PVC achieving Bs2d0 fire rating with solid colour and slightly textured surface, 2 mm thick.
- The level required for biocleaning should be validated for very high infectious risk areas such as operating theatres (*sector 4 according to the Pasteur Institute of Lille France*). The chemical and mark resistance should have been proved on the usual cleaning products according to NF EN ISO 26987. The ease of nuclear decontamination according to DIN 25415 / ISO 8690 should be excellent.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/ BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation sequence: glue as per manufacturer's instructions.



Thermoforming
Complex frame
protection

* For thermoforming of other panels: consult us



* For bend of other panels: consult us



HANDRAILS

Providing a good grip is a priority. SPM handrails have been designed with the greatest of care to aid mobility. Essentially, they are ergonomic, and provide both visual guidance (use of contrast provided by colours) and wall protection. Our systems are available in antibacterial PVC or aluminium and fit any configuration: walls where there are service ducts, curved walls, corners which are not 90°, staircases, while respecting the original decor.



ESCORT DUAL-HEIGHT



ESCORT DUO

SPM handrails protect against hand-borne infections and provide effective help in the fight against the growth of microorganisms and the spread of infection.

Inside establishments open to the public, and especially in health-care institutions, hygiene and the prevention of microbial contamination are permanent concerns. In particular, the hands form a significant vector for the carriage and transmission of contamination, which may be deposited on handrails. According to research, 75 to 90% of in-hospital infection in healthcare establishments may be due to hand-borne transmission.

Laboratory tests carried out by skilled virologists have shown **that SPM's PVC handrails offer 99.96% intrinsic virucidal activity against human coronavirus HCoV-229E** after a contact time of two hours! By way of comparison, the virus is still active on a 304L stainless steel surface after five hours.

The roughness of the handrail, at the junction between profile sections and finishing accessories, collect the majority of contamination and are the most difficult points to clean.

For this reason, all SPM handrails are fitted with bactericidal joints, treated integrally and undamaged by cleaning. Their bactericidal action, proved by an independent laboratory, complements the bacteriostatic and antibacterial properties of our handrails, almost have a smooth finish.




ESCORT-DECOWOOD




ESCORT-PVC SHEATHED



PERFORMER 2



ESCORT + RAPID ANGLE®



ESCORT + RAPID ACCESS®



STARLINE-PVC SHEATHED



LINEA TOUCH-PVC SHEATHED



HANDRAILS

PROTECTION HANDRAILS



ESCORT'DUO p.118-119
Protection handrail
Height 150 mm



LINEA'DUO p.118-119
Protection handrail
Height 150 mm



PERFORMER 2 p.120-121
Protection handrail
Height 140 mm



COMBO'DUO..... p.122-123
Protection handrail
Height 160 mm



STARLINE - PVC SHEATHED p.124-125
Protection handrail with
Decochoc PVC band
Height 90 mm



STARLINE - ANODISED .. p.126-127
Aluminium handrail
with Decowood band
Height 90 mm



with Decotrend band
Height 90 mm



with Decochoc band
Height 90 mm



TUBULAR HANDRAILS



LINEA'TOUCH - PVC SHEATHED p.128-129
Trilobed handrail
Width 40 mm
LED option p.130-131



LINEA'TOUCH - DECOWOOD p.132-133
Wood effect trilobed handrail
Width 40 mm
LED option p.134-135



LINEA'TOUCH - ANODISED p.132-133
Trilobed aluminium handrail
Width 40 mm
LED option p.134-135



ESCORT - PVC SHEATHED p.136-137
Round handrail
Diameter 40 mm




ESCORT - DECOWOOD p.138-139
Wood effect round handrail
Diameter 40 mm



ESCORT - ANODISED p.138-139
Aluminium round handrail
Diameter 40 mm

	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
ESCORT'DUO		Protection handrail	PVC + aluminium	31 colours to combine
LINEA'DUO		Protection handrail	PVC + aluminium	31 colours to combine
PERFORMER 2		Protection handrail	PVC + aluminium	15 colours
COMBO'DUO		Protection handrail	PVC + aluminium	31 colours
STARLINE - PVC SHEATHED		Protection handrail with Decochoc band	PVC-sheathed aluminium + PVC band	33 colours for the band 2 colours for the sheath
STARLINE - ANODISED		Aluminium handrail with Decowood band	Aluminium + wood effect band	7 wood effect decors for the band
STARLINE - ANODISED		Aluminium handrail with Decotrend band	Aluminium + trend effect band	4 trend effect decors for the band
STARLINE - ANODISED		Aluminium handrail with Decochoc band	Aluminium + PVC band	33 colours for the band

	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
LINEA'TOUCH - PVC SHEATED		Trilobed handrail width 40 mm	PVC + aluminium	31 colours
LINEA'TOUCH - DECOWOOD		Wood effect trilobed handrail width 40 mm	PVC + aluminium	6 wood effect decors
LINEA'TOUCH - ANODISED		Trilobed aluminium handrail width 40 mm	Aluminium	Satin silver anodised
ESCORT - PVC SHEATHED		Round handrail diameter 40 mm	PVC + aluminium	31 colours
ESCORT - DECOWOOD		Wood effect round handrail diameter 40 mm	PVC + aluminium	6 wood effect decors
ESCORT - ANODISED		Aluminium round handrail diameter 40 mm	Aluminium	Satin silver anodised (or coated on request)



* and 16 colours with a minimum order quantity

PERFORMER 2

PROTECTION HANDRAIL - 140 MM HIGH

BACTERICIDAL JOINT



APPLICATIONS

Offering both an excellent handgrip and impact resistance for corridors, this protection handrail, is ideal for all public buildings: hospitals, clinics, re-education centres, homes for the elderly.

It benefits from an installation system which facilitates and speeds up the installation.



It is fitted with bactericidal joints (refer to page 114).

SPECIFICATION

- Description: protection handrail (Performer 2 as manufactured by SPM) with quick fixing system, from 3 mm thick smooth and antibacterial PVC achieving Bs2d0 fire rating with solid colour. The height of the handrail is 140 mm, it has an overall protection of 105 mm and a depth of 50 mm. It consists of a completely smooth tubular upper part (diameter 40 mm) and a lower wall protection rail with decorative grooves. A protective film is specified to minimise cleaning before acceptance. The PVC profile snap-fixes onto a continuous aluminium profile, 2 mm thick, and finish is provided by smooth PVC accessories with decorative grooves (wall returns, 90° external angles). The unit is fitted into a PVC fixing spacer thanks to aluminium clamp. It is fitted with bactericidal joints.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixing on PVC spacers to be fitted at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns and external angles fixing with pop rivets.

DESCRIPTION

- Model: Performer 2 protection handrail
- Height: 140 mm
- Length: 4 m
- Tubular upper part diameter: 40 mm
- Depth: 50 mm
- Overall projection: 105 mm
- Stand-off from wall: 55 mm
- Material: 3 mm thick antibacterial and Bs2d0 fire-rated PVC, solid colour, bactericidal joint
- Surface finish:
 - upper handrail: smooth
 - protection rail: with decorative grooves
- Fixing: interlocking into quick fit PVC spacers to be fitted at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard)
- Colours: 15 standard



HANDRAILS



Combo'Duo 160 // 4 colours*



* and 27 colours on request (Please contact us)

COMBO'DUO

PROTECTION HANDRAIL - 160 MM HIGH

BACTERICIDAL JOINT



APPLICATIONS

This product combines handrail and protection rail to ensure a maximum efficiency.

Combo'Duo is perfect for hospitals, clinics or re-education centers, and its slightly textured finish helps to conceal the effect of abrasion and gives it a matte finish.



SPECIFICATION

- Description: protection handrail (Combo'Duo as manufactured by SPM) from 2 mm thick slightly textured (Optimixt grain as manufactured by SPM) and antibacterial PVC achieving Bs2d0 fire rating with solid colour. The height of the handrail is 160 mm, it has an overall protection of 94 mm and a depth of 44 mm. It consists of a tubular upper part (diameter 38 mm) and a lower wall protection rail. The PVC profile snap-fixes onto a continuous aluminium profile and finish is provided by slightly textured PVC accessories (wall returns, 90° internal/external angles). The unit is fitted into a PVC fixing spacer. It is fitted with bactericidal joints.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixing on PVC spacers to be fitted at 0.80 m centres (0.60 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns and angles fixing with self-drilling screws.

DESCRIPTION

- Model: Combo'Duo protection handrail
- Height: 160 mm
- Length: 4 m
- Tubular upper part diameter: 38 mm
- Depth: 44 mm
- Overall projection: 94 mm
- Stand-off from the wall: 50 mm
- Material: 2 mm thick antibacterial and Bs2d0 fire-rated PVC, solid colour, bactericidal joint
- Surface finish: slightly textured ("Optimixt" grain*)
- Fixing: on PVC spacers to be fitted at 0.80 m centres (0.60 m centre in heavy traffic corridors and on light partitions like plasterboard)
- Colours: 4 standard

* "Optimixt" grain: optimal combination of scratch resistance, hygiene and aesthetic.



HANDRAILS



STARLINE - PVC SHEATHED PROTECTION HANDRAIL WITH DECOCHOC PVC BAND 90 MM HIGH

BACTERICIDAL JOINT



APPLICATIONS

A combination of technology and elegant design, the Starline range is the ideal solution for all straight and curved corridor areas in public buildings: hospitals, clinics, retirement homes, hotels, offices.

Starline can be bent for curved sections.

A removeable system is available to provide continuation of the handrail in front of service ducts.




It is fitted with bactericidal joints (refer to page 114).


SPECIFICATION

- Description: PVC sheathed protection handrail with a slightly textured PVC band (Starline - PVC sheathed as manufactured by SPM). The height of the handrail is 90 mm, it has an overall projection of 80 mm and a depth of 30 mm. It consists of a 1.5 mm thick continuous aluminium profile covered by a 1.5 mm thick smooth and antibacterial PVC sheath achieving Bs2d0 fire rating with solid colour. It comprises a groove into which satin silver anodised aluminium brackets, 40 mm deep, curved and perforated with 2-point self-locking, slide and lock. Smooth and antibacterial PVC accessories with solid colour (wall returns, 90° internal and external angle pieces or made-to-measure from 90° to 160°, endcaps), are sleeved into the profile. A self-adhesive slightly textured PVC band, 1 mm thick (Decochoc as manufactured by SPM), is bonded over the rail assembly. It is fitted with bactericidal joints and the profile can be curved.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point self-locking perforated brackets screwed to the wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns, angles and endcaps to be fixed with pop rivets.


DESCRIPTION

- Model: Starline - PVC sheathed, protection handrail with PVC Decochoc band
- Height: 90 mm
- Length: 4 m
- Depth: 30 mm
- Overall projection: 80 mm
- Stand-off from wall: 50 mm
- Material: aluminium profile with an antibacterial and Bs2d0 fire-rated PVC sheath and a PVC band, bactericidal joint
- Fixing: on 2-point self-locking perforated satin silver anodised aluminium brackets, screwed to wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard)
- Colours:
 - 2 standard for profile
 - 33 standard for PVC band







Decowood band
// 7 wood effect decors



Decotrend band
// 4 trend effect decors



Decochoc band
// 33 colours



STARLINE - ANODISED ALUMINIUM HANDRAIL WITH DECOWOOD, DECOTREND OR DECOCHOC BAND - 90 MM HIGH

BACTERICIDAL JOINT



APPLICATIONS

This handrail provides both a good grip and a stylish decorative touch with its wood, trend effect or coloured band. Starline anodised is ideally suited for corridor areas with light traffic of trolleys in public buildings: hospitals, clinics, retirement homes, hotels, offices.

It can be bent for curved sections and a removeable system is available to provide continuation of the handrail in front of service ducts.




It is fitted with bactericidal joints (refer page 114).


SPECIFICATION

- Description: anodised aluminium handrail with a wood, trend or coloured PVC band (Starline - Anodised -Decowood, Decotrend or Decochoc- as manufactured by SPM). The height of the handrail is 90 mm, it has an overall projection of 80 mm and a depth of 30 mm. It consists of a 1.5 mm thick continuous aluminium profile with a groove into which satin silver anodised aluminium brackets, 40 mm deep, curved and perforated with 2-point self-locking, slide and lock. Smooth and antibacterial PVC accessories in silver tone with solid colour (wall returns, 90° internal and external angle pieces or made-to-measure from 90° to 160°, endcaps), are sleeved into the profile. A self-adhesive PVC band, 1 mm thick, wood, trend or coloured (Decowood, Decotrend or Decochoc as manufactured by SPM), is bonded over the rail assembly. It is fitted with bactericidal joints and the profile can be curved.
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point self-locking perforated brackets screwed to the wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns, angles and endcaps to be fixed with pop rivets.

DESCRIPTION

- Model: Starline - Anodised aluminium handrail with wood or trend effect or coloured PVC band
- Height: 90 mm
- Length: 4 m
- Depth: 30 mm
- Overall projection: 80 mm
- Stand-off from wall: 50 mm
- Material: satin silver anodised aluminium profile with wood or trend effect or coloured PVC band, Bs2d0 fire rated, bactericidal joint
- Fixing: on 2-point self-locking perforated satin silver anodised aluminium brackets, screwed to wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard)
- Colours for the band:
 - 7 standard wood decors
 - 4 standard trend decor
 - 33 standard colours





VIRUCIDAL*
99.96%

*virucidal activity against human coronavirus HCoV-229E according to ISO 21702. On our PVC handrails, 99.96% of the virus eliminated after two hours




NEW



Available in LED option (p.130-131)

Linea'Touch - PVC Sheathed // 31 colours



LINEA'TOUCH - PVC SHEATHED TRILOBED HANDRAILS - 40 MM WIDTH

BACTERICIDAL JOINT

BACTERICIDAL
on request

APPLICATIONS

Developed with the help of architects and designers, the Linea'Touch handrail combines design, ergonomics and extreme impact resistance.

Its exclusive trilobed shape, validated by ergonomists, provides an excellent grip while protecting the walls effectively and discreetly.

Thanks to its large choice of accessories and colours for endless combinations, Linea'Touch handrail is also available in a reinforced version in order to offer an unity of design throughout the building, whatever the level of protection required.


Linea'Touch can be used in all public areas, delivering aesthetic harmony from light to heavy traffic areas: hospitals, clinics, retirement homes, hotels, public buildings, offices.

It can be bent and provides various technical solutions for continuity in staircases and in front of service ducts.

It is fitted with bactericidal joints (refer to page 114).

SPECIFICATION

- Description: trilobed handrail with PVC sheath (Linea'Touch or Linea'Touch+ - PVC sheathed as manufactured by SPM) with a cross section from 28 to 40 mm to give it an ergonomic and anti-rotation design. It is 42 mm high, 40 mm width and projects 80 mm from the wall (or 90 mm on request). It consists of a 2 mm thick continuous aluminium profile, or a 5 mm one for the reinforced version, covered by a 2 mm thick smooth and antibacterial, PVC sheath, achieving Bs2d0 fire-rating with solid colour, and a closer underneath. A protective film is specified to minimise cleaning before acceptance. The section comprises a groove into which brackets and closer slide and lock. Wall fixing is by silver anodised effect aluminium brackets with 2-point self-locking: 20 mm wide refined bracket or 55 mm wide bugled bracket (for Linea'Touch) or 80 mm wide reinforced bracket (for the reinforced Linea'Touch+). Wall fixing is also available by swan-neck with 70 mm rose brackets, in brushed stainless steel, 3 point self-locking. The axial position of the brackets provides an excellent guiding. Various smooth and antibacterial PVC accessories achieving Bs2d0 fire-rating with solid colour (flat or beveled endcaps, classic or extended and curved wall returns, 90° internal/external angle or made-to-measure from 90° to 135°), supplied with bactericidal joints, are available to finish the handrail assembly and are sleeved into the profile with clamping screws. All technical solutions are available to ensure continuity around corners (90° or made-to-measure), in staircases [3-way "universal joint" rotation angle -Rapid'Angle® as manufactured by SPM, across service ducts (quick removable assembly wedge) and around curved sections (pre-curved in the factory). These handrails achieve an impact resistance in excess of 70 Joules -i.e. an impact of more than 220 kg travelling at 2 kmh- (for Linea'Touch) and of 110 Joules -i.e. an impact of more than 320 kg travelling at 2 kmh- (for the reinforced version Linea'Touch+).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point or 3-point self-locking brackets, depending on the model, screwed to the wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns, endcaps and angles to be fixed with 2.5 mm Allen clamping screws.



VALIDATED BY
ERGONOMISTS

DESCRIPTION

- Model: Linea'Touch or Linea'Touch+ (reinforced version) - PVC sheathed - trilobed handrail
- Cross section: height 42 x width 40 mm
- Length: 4 m
- Overall Projection: 80 mm (90 mm on request)
- Stand-off from wall: 40 mm (50 mm on request)
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, on continuous aluminium profile, bactericidal joint
- Fixing: on self-locking brackets - refined, bugled or reinforced, 2-point fixing in aluminium, silver anodised effect
- swan-neck with 70 mm rose, 3 point fixing in brushed stainless steel screwed to the wall every 1.20 m (0.80 m centres in heavy traffic areas and on light partitions like plasterboard)
- Colours: 31 standard





Bs2d0



100%
antibacterial




100%
recyclable



Specifications and section drawings on our website www.spm-international.com
bimobject BimObject in Revit and Archicad

HANDRAILS





VIRUCIDAL*
99.96%

*virucidal activity against human coronavirus HCoV-229E according to ISO 21702. On our PVC handrails, 99.96% of the virus eliminated after two hours



LINEA'TOUCH LED - PVC SHEATHED TRILOBED HANDRAILS - 40 MM WIDTH

BACTERICIDAL JOINT

BACTERICIDAL
on request

APPLICATIONS

The new Linea'Touch LED handrail is designed to help people move around safely in corridors and traffic areas. Thanks to its exclusive trilobed shape, developed with our partner architects and validated by ergonomists, the Linea'Touch LED handrail provides an excellent handgrip while protecting walls effectively and now offers a user guiding system thanks to integrated lighting.

Ideal in hospitals, clinics, retirement homes, disability centers, performance venues, hotels, offices, etc., the LED handrail provides comfort and safety for your users and staff, along with design and aesthetics for your establishment. With Linea'Touch LED, create your customised ambiance, for each area, department or floor.



The Linea'Touch LED handrail operates with a 24 VDC 60 W dimmable power supply box for a maximum handrail length of 8 meters. The internal/external angle pieces have an integrated power cable for connection with the LED bands. The power supply can be placed in a false ceiling or electrical cabinet for easier maintenance (intervention by an electrician is recommended). A switch, programmer or proximity sensor can be associated with the handrail.

Refer to the Installation Procedures.

It is fitted with bactericidal joints (refer to page 114).

DESCRIPTION


- Model: Linea'Touch LED - PVC sheathed - trilobed handrail
- Cross section: height 42 mm x width 40 mm
- Length:
 - Handrail: 4 m
 - LED band: 5 m (cuttable)
 - Coloured filter: 1 m
- Overall Projection: 80 mm
- Stand-off from wall: 40 mm
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, on continuous aluminium profile, bactericidal joint
- Fixing: on bugled and quick removable 2-point self-locking aluminium brackets, silver anodised effect, screwed to the wall every 1.20 m (0.80 m centres in heavy traffic areas and on light partitions like plasterboard)
- Colours:
 - 31 standard for the handrail
 - 5 standard for the optional coloured filter



55 mm bugled
Quick removable self-locking aluminium bracket silver anodised effect

Linea'Touch LED - Coloured filter
// 5 colours

NEW



Linea'Touch LED - PVC sheathed
// 31 colours




SPECIFICATION

Package: Carpentry/Joinery


- Description: trilobed handrail with PVC sheath and lighting LED system (Linea'Touch LED - PVC sheathed as manufactured by SPM) with a cross section from 28 to 40 mm to give it an ergonomic and anti-rotation design. It is 42 mm high, 40 mm width and projects 80 mm from the wall. It consists of a 2 mm thick continuous aluminium profile, covered by a 2 mm thick smooth and antibacterial PVC sheath, achieving Bs2d0 fire-rating with solid colour, a wire connector, a LED band of 5 meters which can be cut every 50 mm, and a closer underneath. A protective film is specified to minimise cleaning before acceptance. The section comprises a groove into which brackets and closer slide and lock. A colour filter (colour selected by architects from manufacturer's standard range) can be inserted between the LED band and the closer. Wall fixing is by quick removable silver anodised effect aluminium bugled brackets with 2-point self-locking, 55 mm wide. The axial position of the brackets provides an excellent guiding. Various smooth and antibacterial PVC accessories, achieving Bs2d0 fire-rating with solid colour, (classic wall returns, 90° internal/external angles or made-to-measure from 90° to 135°), supplied with bactericidal joints, are available to finish the handrail assembly and are sleeved into profile with clamping screws. Technical solutions are available to ensure continuity around corners (90° or made-to-measure with integrated wire connector). In staircases (3-way "universal joint" rotation angle - Rapid'Angle® as manufactured by SPM) and across service ducts (Quick-removable assembly wedge) continuity is ensured without LED system. This handrail achieves an impact resistance in excess of 70 Joules -i.e. an impact of more than 220 kg travelling at 2 km/h.
- Norms: CE compliant with European Directives, Class III (LED only).
- Environment:
 - Electrical components (LED bands and cables): compliant with RoHS Directive.
 - Handrail and accessories: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point quick removable assembly self-locking 55 mm bugled bracket in aluminium screwed to the wall every 0.80 m to 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns and angles to be fixed with 2.5 mm Allen clamping screws. Operates with a dimmable 24 VDC constant voltage power supply box with sufficient power for a LED band of 9.6W/m (dimmable driver 24 VDC 60W as supplied by SPM). The power supply and the electrical connection belong to the Electrical installation package.


Package: Electrical installation

- The trilobed handrail with lighting LED system (Linea'Touch LED - PVC sheathed as manufactured by SPM), operates with a dimmable 24 VDC constant voltage power supply box with sufficient power for a LED band of 9.6W/m (dimmable driver 24 VDC 60W as supplied by SPM) which gets the following characteristics:
 - Output voltage Uout: 24 VDC
 - Max power: 60 W
 - Maximum length: 8 m
 - Graduation technology: 0-10 V PWM Resistance
 - Dimensions: 150 x 53 x 35 mm
- The power supply and the electrical connection belong to the Electrical installation package.



55 mm bugled
Quick removable self-locking aluminium bracket silver anodised effect





LINEA'TOUCH LED - DECOWOOD & ANODISED BACTERICIDAL JOINT TRILOBED HANDRAILS - 40 MM WIDTH

APPLICATIONS

The new Linea'Touch LED handrail is designed to help people move around safely in corridors and traffic areas. With a wood effect or satin silver anodised aluminium finish, the Linea'Touch LED handrails combine design, ergonomics and elegance. Thanks to its exclusive trilobed shape, developed with our partner architects and validated by ergonomists, Linea'Touch LED handrail provides an excellent handgrip and now offers a user guiding system thanks to integrated lighting.

Ideal in hospitals, clinics, retirement homes, disability centers, performance venues, hotels, offices, etc., the LED handrail provides comfort and safety for your users and staff, along with design and aesthetics for your establishment. With Linea'Touch LED, create your customised ambiance, for each area, department or floor.

The Linea'Touch LED handrail operates with a 24 VDC 60 W dimmable power supply box for a maximum handrail length of 8 meters. The internal/external angle pieces have an integrated power cable for connection with the LED bands. The power supply can be placed in a false ceiling or electrical cabinet for easier maintenance (intervention by an electrician is recommended). A switch, programmer or proximity sensor can be associated with the handrail.

Refer to the Installation Procedures.

It is fitted with bactericidal joints (refer to page 114).

DESCRIPTION

- Model: Linea'Touch LED – Decowood or Linea'Touch LED – Anodised – trilobed handrail
- Cross section: height 42 mm x width 40 mm
- Length:
 - Handrail: 4 m
 - LED band: 5 m (cuttable)
 - Coloured filter: 1 m
- Overall Projection: 80 mm
- Stand-off from wall: 40 mm
- Material: 10 micron satin silver anodised aluminium or wood effect PVC, bactericidal joint
- Fixing: on bugled and quick removable 2-point self-locking aluminium brackets, silver anodised effect, screwed to the wall every 1.20 m (0.80 m centres in heavy traffic areas and on light partitions like plasterboard.)
- Colours:
 - 6 wood effect standard decors for Linea'Touch LED – Decowood
 - Satin silver anodised for Linea'Touch LED – Anodised
 - 5 standard for the optional coloured filter



SPECIFICATION


Package: Capentry/Joinery

- Description: trilobed wood effect or satin silver anodised aluminium handrail with lighting LED system (Linea'Touch LED – Decowood or Linea'Touch LED – Anodised as manufactured by SPM) with a cross section from 28 to 40 mm to give it an ergonomic and anti-rotation design. It is 42 mm high, 40 mm width and projects 80 mm from the wall. It consists of a 2 mm thick aluminium profile covered with wood effect PVC fil (Linea'Touch – Decowood) or of a 2 mm satin silver anodised aluminium (Linea'Touch – Anodised), achieving Bs2d0 fire-rating, a wire connector, a LED band of 5 meters which can be cut every 50 mm, and a closer underneath. The section comprises a groove into which brackets and closer slide and lock. A colour filter (colour selected by architects from manufacturer's standard range) can be inserted between the LED band and the closer. Wall fixing is by quick removable silver anodised effect aluminium bugled brackets with 2-point self-locking, 55 mm wide. The axial position of the brackets provides an excellent guiding. Various smooth and antibacterial PVC accessories, achieving Bs2d0 fire-rating with solid colour, (classic wall returns, 90° internal/external angles or made-to-measure from 90° to 135°), supplied with bactericidal joints, are available in anodised look to finish the handrail assembly and are sleeved into profile with clamping screws. Technical solutions are available to ensure continuity around corners (90° or made-to-measure with integrated wire connector). In staircases (3-way "universal joint" rotation angle - Rapid'Angle® as manufactured by SPM) and across service ducts (Quick-removable assembly wedge) continuity is ensured without LED system. This handrail achieves an impact resistance in excess of 70 Joules -i.e. an impact of more than 220 kg travelling at 2 km/h.
- Norms: CE compliant with European Directives, Class III (LED only).
- Environment:
 - Electrical components (LED bands and cables): compliant with RoHS Directive.
 - Handrail and accessories: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point quick removable assembly self-locking 55 mm bugled bracket in aluminium screwed to the wall every 0.80 m to 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns and angles to be fixed with 2.5 mm Allen clamping screws. Operates with a dimmable 24 VDC constant voltage power supply box with sufficient power for a LED band of 9.6W/m (dimmable driver 24 VDC 60W as supplied by SPM). The power supply and the electrical connection belong to the Electrical installation package.





Package: Electrical installation

- The trilobed handrail with lighting LED system (Linea'Touch LED – Decowood or Anodised as manufactured by SPM), operates with a dimmable 24 VDC constant voltage power supply box with sufficient power for a LED band of 9.6W/m (dimmable driver 24 VDC 60W as supplied by SPM) which gets the following characteristics:
 - Output voltage Uout: 24 VDC
 - Max power: 60 W
 - Maximum length: 8 m
 - Graduation technology: 0-10 V PWM Resistance
 - Dimensions: 150 x 53 x 35 mm
- The power supply and the electrical connection belong to the Electrical installation package.

LINEA'TOUCH DECOWOOD




LINEA'TOUCH ANODISED





Escort - PVC Sheathed // 31 colours



ESCORT - PVC SHEATHED ROUND HANDRAIL - DIAMETER 40 MM

BACTERICIDAL JOINT



APPLICATIONS

Escort is designed to provide a high quality grip and classic look. Highly appreciated by mobility-impaired persons for its perfect roundness and pleasant feel.

Escort is ideal for all corridors and stairways in retirement homes, hospitals, clinics, rehabilitation centres, collective housing.

Escort can be bent for curved sections and a removeable system is available to provide continuation of the handrail in front of service ducts.






It is fitted with bactericidal joints (refer to page 114).

SPECIFICATION

- Description: round handrail with PVC sheath (Escort - PVC sheathed as manufactured by SPM) with a diameter of 40 mm and an overall projection and height of 80 mm. It consists of a 1.5 mm thick continuous aluminium profile covered by a 1.5 mm thick smooth and antibacterial PVC sheath achieving Bs2d0 fire rating with solid colour, and a matching closer underneath. A protective film is specified to minimise cleaning before acceptance. The section comprises a groove into which brackets and matching closer slide and lock. Wall fixing is by 40 mm deep satin silver anodised aluminium brackets with 2-point self-locking: curved and perforated (80 mm wide), curved and full (60 mm wide) or bugled (55 mm wide). Wall fixing is also available by swan-neck with 70 mm rose brackets, in brushed stainless steel, 3 point self-locking. Various smooth and antibacterial PVC accessories with solid colour (round or flat endcaps, external and internal 90° angle pieces or made-to-measure from 90 to 165°, wall returns), supplied with bactericidal joints, are available to finish the handrail assembly and are sleeved into the profile. All technical solutions are available to ensure continuity around corners (90° or made-to-measure), in staircases (slope link or 3-way "universal joint" rotation angle -RapidAngle® as manufactured by SPM-), across service ducts (quick removable assembly wedge or articulated link -RapidAccess® as manufactured by SPM-) and around curved sections (pre-curved in the factory).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011 Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point or 3-point self-locking brackets, depending on the model, screwed to the wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns, endcaps and angles to be fixed with 2.5 mm Allen clamping screws.


DESCRIPTION

- Model: Escort - PVC sheathed - round handrail
- Diameter: 40 mm
- Length: 4 m
- Overall projection: 80 mm (or 90 mm on request)
- Stand-off from wall: 40 mm (or 50 mm on request)
- Material: antibacterial and Bs2d0 fire-rated PVC, solid colour, on continuous aluminium profile, bactericidal joint
- Fixing: on self-locking brackets
 - perforated, bugled or full, 2-point fixing in satin silver anodised aluminium
 - swan-neck with 70 mm rose, 3 point fixing in brushed stainless steel
- screwed to wall at 1.20 m centres (0.80 m centres in heavy traffic areas and on light partitions like plasterboard)
- Colours: 31 standard



Specifications and section drawings on our website www.spm-international.com
BimObject in Revit and Archicad





ESCORT - DECOWOOD & ANODISED ROUND HANDRAILS - DIAMETER 40 MM

BACTERICIDAL JOINT



APPLICATIONS


Particularly elegant handrails with a wood effect or satin silver anodised aluminium finish and curved, unobtrusive brackets. They are ideal for all buildings open to the public: corridors and stairways in retirement homes, schools, hotels, residential apartment buildings, offices, etc.

Escort can be bent for curved sections. A removeable system is available to provide continuation of the handrail in front of service ducts.

They are fitted with bactericidal joints (refer to page 114).



SPECIFICATION

- Description: round wood effect handrail (Escort - Decowood as manufactured by SPM) or satin silver anodised aluminium (Escort - Anodised as manufactured by SPM) with a diameter of 40 mm and an overall projection and height of 80 mm. It consists of a 1.5 mm thick continuous aluminium profile and a matching closer underneath. The section comprises a groove into which brackets and matching closer slide and lock. Wall fixing is by 40 mm deep satin silver anodised aluminium brackets with 2-point self-locking: curved and perforated (80 mm wide), curved and full (60 mm wide) or bugled (55 mm wide). Wall fixing is also available by swan-neck with 70 mm rose brackets, in brushed stainless steel, 3 point self-locking. Various smooth and antibacterial PVC accessories (round or flat endcaps, external and internal 90° angle pieces or made-to-measure from 90 to 165°, wall returns), supplied with bactericidal joints, are available in wood effect or anodised look or chromium look to finish the handrail assembly and are sleeved into the profile. All technical solutions are available to ensure continuity around corners (90° or made-to-measure), in staircases (slope link or 3-way "universal joint" rotation angle -RapidAngle® as manufactured by SPM-), across service ducts (quick removable assembly wedge or articulated link -RapidAccess® as manufactured by SPM-) and around curved sections (pre-curved in the factory).
- Environment: no heavy metals and no substance potentially subjected to any REACH restriction are used in its manufacture, nor PBT/BPA. The calcium-zinc thermal stabilisation process is used. The emission level of volatile substance in inside air has been tested according to ISO 16000-6 and is very low (A+) according to the French regulation (23 March 2011 nr 2011-321 Decree and 19 April 2011Order). 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: upper edge of section 0.90 m max. above floor level. Fixes to 2-point or 3-point self-locking brackets, depending on the model, screwed to the wall at 1.20 m centres (0.80 m centres in heavy traffic corridors and on light partitions like plasterboard). Wall returns, endcaps and angles to be fixed with 2.5 mm Allen clamping screws.



DESCRIPTION

- Model: Escort - Decowood or Escort - Anodised round handrail
- Diameter: 40 mm
- Length: 4 m
- Overall projection: 80 mm (or 90 mm on request)
- Stand-off from wall: 40 mm (or 50 mm on request)
- Material: 10 micron satin silver anodised aluminium or wood effect PVC, bactericidal joint
- Fixing: on self-locking brackets
 - perforated, bugled or full, 2-point fixing in satin silver anodised aluminium
 - swan-neck with 70 mm rose, 3 point fixing in brushed stainless steel screwed to wall at 1.20 m centres (0.80 m centres in heavy traffic areas and on light partitions like plasterboard)
- Colours:
 - 6 wood effect standard decors for Escort - Decowood
 - satin silver anodised for Escort - Anodised
 - coating on request



SPECIFIC PROTECTION

INDIVIDUAL PROTECTION



SAFY'CORNER p.141
90° adhesive cushioning corner protector




SAFY'HAND p.143
Hands-free door opener



SAFY'DOOR p.142
Door finger protection system



	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
SAFY'CORNER		90° adhesive cushioning corner protector	Elastomer	4 colours
SAFY'DOOR	-	Door finger protection system	Elastomer	4 colours
SAFY'HAND		Hands-free door opener	Coated aluminium	1 colour



Safy'Corner // 4 colours



SAFY'CORNER
90° ADHESIVE CUSHIONING CORNER PROTECTOR



APPLICATIONS

The Safy'Corner cushioning corner protector is designed to protect persons from impacts against a protruding corner. Made from a flexible elastomer, it has a high impact absorption capacity and minimises the risk of injury. It has two strips of double-sided adhesive tape and a protective film for ease of installation and cleaning.



Ideal for childcare settings, retirement homes, specialist institutions, gyms and sports halls.

DESCRIPTION

- Model: Safy'Corner adhesive cushioning corner protector
- Angle: 90°
- Wing width: 25 mm (internal measurement)
- Thickness: 11 mm
- Length: 1.30 m
- Material: solid colour elastomer
- Surface finish: smooth
- Fixing: adhesive foam tapes
- Colours: 4 standard

SPECIFICATION

- Description: 25 mm wide wings (internal measurement) 90° adhesive cushioning corner protector (Safy'Corner as manufactured by SPM) comprising a 10 mm thick smooth and flexible elastomer section with solid colour, covered with a 1 mm thick transparent protective film to reduce cleaning throughout its service life. It is provided with 2 strips of adhesive foam tape for fixing. It has an impact absorption capacity of 38%, thus minimising the risk of injury.
- Environment: no heavy metals are used in its formulation, nor PBT/BPA. 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: adhesive.



SPECIFIC PROTECTION

Hinge side

Rabbit side

Safy'Door // 4 colours



Safy'Hand // 1 colour

NEW

Yellow

SAFY'DOOR

DOOR FINGER PROTECTION SYSTEM



SAFY'HAND

HANDS-FREE DOOR OPENER



APPLICATIONS

The door finger protection system Safy'Door is the ideal solution for making both single and swing doors safe.

The special shape of the strong, flexible bellows prevents fingers from getting into door rabbets.


The door finger protection system Safy'Door improves safety in locations frequented by young children as well as in workplaces, preventing a major cause of accidents and protecting staff from often serious after-effects.

DESCRIPTION

- Model: Safy'Door door finger protection system
- Height: 1.40 m
- Width: 170 mm (rabbet side) and 70 mm (hinge side)
- Material: 2 mm thick solid colour elastomer
- Surface finish: smooth
- Fixing: on pre-drilled aluminium cores
- Colours: 4 standard

SPECIFICATION

- Description: door finger protection system (Safy'Door as manufactured by SPM) to prevent fingers being trapped when opening and closing doors, comprising two solid colour, flexible elastomer sections 1.40 m in height, that slot into two pre-drilled aluminium cores. The 7-bellows section is used on the inside door jamb (rabbet side) and can cover a 150-mm gap, with the bellows providing additional extension up to 190 mm. The 3-bellows section is used on the outside door jamb (hinge side) and is designed to move with the door, compressing on opening by 20 to 80 mm.
- Environment: no heavy metals are used in its formulation, nor PBT/BPA. 100% of the product are recyclable.
- Colour: selected by architects from manufacturer's standard range.
- Installation method: snap-fixes onto pre-drilled aluminium cores screwed to the door and frame.



APPLICATIONS

Safy'Hand hands-free door opener is the hygienic solution to limit the spread of viruses and the risks of manual contamination. It allows to open and close the doors without hands contact, with the elbow or the forearm.

Ideal for healthcare establishments, schools and nurseries, Safy'Hand is quick and easy to install. It adapts to the (round) existing door handle and its yellow coated surface will facilitate cleaning and disinfection.



DESCRIPTION

- Model: Safy'Hand hands-free door opener, for round door handle
- Height: 45 mm
- Width: 55 mm
- Depth: 63.5 mm
- Diameter: from 17 to 24 mm
- Material: coated aluminium
- Fixing: with four hexagon counter-sunk head screws, 2.5 mm Allen end (supplied)
- Colour: yellow

INSTALLATION PROCEDURE

Quick and easy installation:

1. Unscrew the four Hex screws using a 2.5 mm Allen key
2. Insert on the round handle and position Safy'Hand system
3. Screw the four Hex screws to hold Safy'Hand system



SPECIFIC PROTECTION



SPECIFIC PROTECTION

INDUSTRIAL PROTECTION



ELASTO'FLEX 100V p.145
Variable angle corner protector



ELASTO'PUNCH 200E p.146
Wall protection rail
Height 200 mm



ELASTO'PUNCH 100D p.147
Wall protection rail
Height 100 mm



	CODE	DESCRIPTION	MATERIAL	COLOUR RANGE
ELASTO'FLEX 100V		Variable angle corner protector	Thermoplastic elastomer	1 colour
ELASTO'PUNCH 200E		Wall protection rail	Thermoplastic elastomer	1 colour
ELASTO'PUNCH 100D		Wall protection rail	Thermoplastic elastomer	1 colour



Elasto'Flex 100V // 1 colour



ELASTO'FLEX 100V
VARIABLE ANGLE CORNER PROTECTOR



APPLICATIONS



The Elasto'Flex 100V corner protector is a highly resistant protection for the 45° to 135° corners of your industrial buildings. It blends in perfectly with all types of areas subject to severe impacts, and its black elastomer material enables it to be used both indoor and outdoor.

DESCRIPTION

- Model: Elasto'Flex 100V variable angle corner protector
- Angle: from 45 to 135°
- Wing width: 100 mm
- Thickness: from 4 mm (end) to 10 mm (corner)
- Length: 3 m
- Material: non-rigid thermoplastic elastomer, solid colour
- Surface finish: smooth
- Fixing: by screwing
- Colour: black

SPECIFICATION

- Description: variable angle corner protector (from 45° to 135°) in non-rigid and smooth thermoplastic elastomer, 100 mm wing width (external measurement) / 90 mm wing width (internal measurement) (Elasto'Flex 100V as manufactured by SPM) comprising a profile, from 4 mm (end) to 10 mm (corner), solid colour, giving it excellent impact-resistance properties and good ageing and UV resistance.
- Environment: no heavy metals are used in its formulation, nor PBT/BPA. 100% of the product are recyclable.
- Colour: black.
- Installation method: by screwing.



SPECIFIC PROTECTION





Elasto'Punch 200E // 1 colour

Black



Elasto'Punch 100D // 1 colour

Black

ELASTO'PUNCH 200E

WALL PROTECTION RAIL - 200 MM HIGH



APPLICATIONS

With its dense shape, the Elasto'Punch 200E protection rail provides effective protection for walls that are very exposed to side impacts and abrasion from guided trucks, in logistics corridors, storage areas and warehouses, car parks, etc.



Its black elastomer material enables it to be used both indoor and outdoor.

DESCRIPTION

- Model: Elasto'Punch 200E protection rail
- Height: 200 mm
- Depth: 30 mm
- Length: 3 m
- Material: non-rigid thermoplastic elastomer, 15 to 30 mm thick, solid colour
- Surface finish: smooth
- Fixing: by screwing
- Colour: black

SPECIFICATION

- Description: E-shaped flat protection rail in non-rigid and smooth thermoplastic elastomer (Elasto'Punch 200E as manufactured by SPM) comprising a 200 mm height profile, 15 to 30 mm thick, solid colour, giving it excellent impact-resistance properties and good ageing and UV resistance.
- Environment: no heavy metals are used in its formulation, nor PBT/BPA. 100% of the product are recyclable.
- Colour: black.
- Installation method: by screwing.



ELASTO'PUNCH 100D

WALL PROTECTION RAIL - 100 MM HIGH



APPLICATIONS

The Elasto'Punch 100D protection rail is designed to protect your industrial buildings. Its black elastomer material enables it to be used both indoor and outdoor.



Ideally installed on loading docks, it will absorb impacts from heavy goods vehicles.

DESCRIPTION

- Model: Elasto'Punch 100D protection rail
- Height: 100 mm
- Depth: 90 mm
- Length: 3 m
- Material: non-rigid thermoplastic elastomer, 14 mm thick, solid colour
- Surface finish: smooth
- Fixing: by screwing
- Colour: black

SPECIFICATION


- Description: D-shaped round protection rail in non-rigid and smooth thermoplastic elastomer (Elasto'Punch 100D as manufactured by SPM) comprising a 100 mm height profile, 90 mm deep, solid colour and 14 mm thick, giving it excellent impact-resistance properties and good ageing and UV resistance. Finish is provided by end pieces and screw-cover blanking plugs in smooth thermoplastic elastomer.
- Environment: no heavy metals are used in its formulation, nor PBT/BPA. 100% of the product are recyclable.
- Colour: black.
- Installation method: by screwing.




SPECIFIC PROTECTION



Decochoc H₂O // 5 standard colours



Decochoc // 33 colours



* with a minimum order quantity.

SOLUTIONS FOR PANELS

THERMOWELDING

HOT WELDED JOINTS

APPLICATIONS

SPM Decochoc, Decowood, Decotrend, Decoclean and Decochoc H₂O panels are made of antibacterial PVC. They are easy to clean and can be installed:

- from floor to ceiling with welded joints,
- in right or rounded angles, irrespective of the degrees or the radius,
- above the covings of PVC floor coverings.

For a reliable watertightness, SPM has a range of welding rods matched to the colours of SPM profiles, allowing you to thermoweld one panel to another.

SPM and GERFLOR also provide a global solution for absolute watertightness and reliable junction: hot welded joints between the coving of the floor covering and the wall panel.

This system is optimised to work with the exclusive GERFLOR Corner System, and is particularly recommended for operating rooms and other rooms requiring a high level of hygiene.

DESCRIPTION

- Model: SPM welding rod
- Diameter: 4 mm
- Length: 100 m roll
- Material: flexible PVC
- Fixing: hot welded with welding machine
- Colours:
 - 33 standard for Decochoc
 - 5 standard for Decochoc H₂O




THERMOFORMING

PILLAR AND DOOR FRAME PROTECTION

WITH DECOCHOC, DECOSMIC, DECOWOOD AND DECOTREND PANELS

APPLICATIONS

In order to adapt to all building layouts, Decochoc, Decosmic, Decowood and Decotrend panels can be thermoformed to cover round pillars (diameter less than 800 mm) and complex door frames that can not be protected with simple L or U bends.



FIXING



SPM universal primer
(100 to 150 g required per m²)
5 l drum



SPM acrylic glue - Simple bonding
Solvent-free
(300 to 350 g required per m²) - Available in 6 or 14 kg jars



SPM multipurpose adhesive sealant
Solvent-free
290 ml cartridge (about 25 ml of cord)



Double-sided foam adhesive roll 4957/15 mm wide
(contact us prior to use)
25 m roll



Double-sided adhesive roll 4970/50 mm wide
For installation on doors or laminates
(contact us prior to use) - 50 m roll



Silicone joint for Decochoc, Decosmic, Decowood, Decotrend, Decoclean, and Decochoc H₂O panels (matching colours)
310 ml cartridge



Welding rod for Decochoc, Decowood, Decotrend, Decoclean and Decochoc H₂O panels (matching colours)
100 m roll

For further information about installation of SPM accessories and use of glues, silicon joints and welding rods, please consult our Installation Procedure Guide.



SOLUTIONS FOR HANDRAILS


IN FRONT OF SERVICE DUCTS

APPLICATIONS

Quick-removable system (assembly wedges) designed to make easy access to service duct gates whilst providing continuation of the handrails and secure handgrip for people.

Available for Escort, Linea'Touch and Starline handrails.


SERVICE DUCT GATES LONGER THAN 1100 MM



It is necessary to place a quick-removable bracket onto the service duct access gate.

STARLINE HANDRAIL


For Starline handrail, SPM can provide a ready-to-install kit (section up to 1100 mm ; other dimensions on request).




Section of Starline profile (up to 1100 mm), especially machined for service duct. (Other dimensions available on request)

ESCORT AND LINEA'TOUCH HANDRAILS

For Escort and Linea'Touch handrails, the service duct kit is installed on site: by cutting the profile to the length of the access gate using two 45° cuts and two quick-removable assembly wedges.




For Escort handrail, Rapid'Access®, the articulated link has been especially designed for service duct, to complete with one quick-removable assembly wedge. (available in chalk or anodised look)




CURVING

APPLICATIONS


Curving of Starline, Linea'Touch and Escort handrails to fit in different building layouts.



CONVEX Curve



CONCAVE Curve




JOINTING ACCESSORY

APPLICATIONS

Aluminium jointing piece with bactericidal joint to bring perfectly into line and to hold tight between two straight lengths of Escort or Linea'Touch handrails.

ESCORT

also available for the handrail Linea'Touch.




RAPID'ANGLE® FOR STAIRCASES AND FOR 80° TO 180° ANGLES

APPLICATIONS


SPM has developed Rapid'Angle® for Escort round handrail and for Linea'Touch trilobed handrail especially designed:

- to fit in all staircase layouts with slope link and angled slop link: rotating 3D
- to fit all angles: modular from 80° to 180°



RAPID'ANGLE® ESCORT

also available for the handrail Linea'Touch.




DUAL-HEIGHT SPECIAL "ACCESSIBILITY" BRACKET: ESCORT

APPLICATIONS

This dual-height bracket simplifies the installation of Escort handrails at two heights: one at the standard height and the other for children and/or those using wheelchairs. The height of the lower handrail has been specially designed to provide a comfortable aid to help such people to move around.



This accessory simplifies installation since only one set of horizontal marking outs is required for two levels of handrails.



TACTILE MARK: ESCORT

APPLICATIONS

Unique design for this assembly wedge of tactile mark to be fitted in under the Escort handrail to provide locating help to visually impaired persons. Repeated, it helps indicate the where on the floor we are.



To help with the installation of SPM handrails, consult the installation procedures guide available upon request.



TOOLS

LEISTER WALL WELDING CASE

Professional welding case includes all the tools required to create perfect welding rods between SPM panels or between SPM panels and PVC floor coving.



CONTAINS

1. Leister electronic welding gun and a spare resistor
2. Narrow rapid nozzle diameter 4/5 mm
3. Triangular rapid nozzle diameter 4/5 mm
4. Nozzle brush (length 160 mm)
5. Mozart 2-in-1 trimming knife and 5 replacement blades
6. Triangular groover (length: 24 cm - 6 cm sides)
7. Trimming groover with rounded blade



HOOKED BLADE CUTTER

This cutter's unique blade shape makes it ideal for cutting PVC panels and profiles.

DESCRIPTION

- Aluminium/plastic cutter
- Length 140 mm
- Includes tungsten carbide hooked blade and all-purpose blade



TWO-HANDLED SMOOTHING ROLLER

Ideal for smoothing SPM panels after applying adhesive; offers substantial finishing pressure with its double handle and ease of use.

DESCRIPTION

- Roller length: 160 mm
- Roller diameter: 40 mm
- Dimensions (L x W x H): 210 mm x 180 mm x 120 mm



THERMOBENDING MACHINES

Specially designed and developed for bending SPM panels on-site. Available in 2 sizes for making bendings over lengths of up to 1.30 m or 3.00 m. Larger model equipped with rotary stop block. Comes in case for easy transport and storage.



DESCRIPTION

Bending length in mm	1300	3000
Dimensions in mm (L x l x H)	1900 x 700 x 300	3600 x 700 x 300
Weight in kg	35	90
Voltage in V	220	220



i INFO: THERMAL EXPANSION

PVC has a coefficient of thermal expansion to take into account when installing. If products are stored in unheated premises in winter or exposed to sun in summer, they must be stored at the same temperature as the premises in which they are to be fitted for at least 24 hours.

If the products are to be installed in temperature conditions very different to 20°C (such as unheated permises in winter), take into account dimensional variations indicated in the below table.

Temperature in °C	Dimensional variations in mm for 1 linear meter	Comments
15	-1	Minimum temperature
20 (ideal temperature)	0	Ideal temperature
25	+1	Admissible temperature
30	+2	Maximum temperature

For detailed instructions, please refer to Installation Procedure Guide.







MAGNIN CLINIC (New Caledonia)
Decochoc panel / Escort handrail / Cornea corner protector
SANAE Architecture - Photographer: Eric Dell'Erba



HOSPITAL - MEAUX (France)
Decoprint panel
Architect: Pascale Seurin



MATERNITY WARD - TROUSSEAU HOSPITAL - PARIS (France)
LineaTouch LED handrail / Decochoc panel / Profila corner protector
Engineers: Flore Chauvet & Christophe Lafreiney



1

HOSPITAL - POITIERS (France)
Decoprint & Decochoc panels / Escort handrail /
Protecta 2 corner protector
Architect: La Nouvelle Tannerie
1/2/3



MEMORIAL HOSPITAL - SAINT LÔ (France)
Decoprint panel



2




3

RETIREMENT HOMES DISABILITY CENTERS



EHPAD - VILLENEUVE LES BÉZIER (France)
Decochoc panel
Photographer: Fabrice Maillard



EHPAD ADEF - HUSSIGNY (France)
Decowood panel / Escort Decowood handrail
Architect: François Maignan




EHPAD LAURY MUNCH - STRASBOURG (France)
Thermoformed Decochoc panel



LIFE CENTER - BASSILAC (France)
Decowood panel



Escort handrail
with Rapid'Angle®



EHPAD - CORDES SUR CIEL (France)
Decochoc panel / Linea'Touch handrail / Profila corner protector

EARLY
CHILDHOOD



CHILDHOOD CENTER - DÉOLS (France)
Decofresc panel



NEGRENEYS CRÈCHE - TOULOUSE (France)
Decochoc panel / Profila corner protector



ICHTERSHAUSEN CRÈCHE (Germany)
Decokid & Decochoc panels



1
LOCAL CRÈCHE - CARMAUX (France)
Decochoc & Decofresc panels / Profila corner protector / SafyDoor door finger protection 1/2




NEGRENEYS CRÈCHE - TOULOUSE (France)
Decochoc panel / Profila corner protector





2

EDUCATION



SPORT FITNESS



HOUSING



Decochoc panel with inlaid signage / Protecta 2 corner protector / Handplate



Decochoc H₂O panel



Decochoc H₂O panel



OPH - BOBIGNY (France)
Decochoc panel with inlaid signage / Fin'Color finishing profile



Decowood panel with inlaid signage / Profil'Inox corner protector



AVEYRON HABITAT (France)
Decochoc & Decowood panels

HOTELS
CATERING




MERCURE COMPANS HOTEL - TOULOUSE (France)
Decoprint, Decotrend & Decowood panels /
Inlaid signage / Contact plate
Trace Architects
1/2/3/4



1



1



2

MERCURE WILSON HOTEL - TOULOUSE (France)
Decochoc & Decotrend panels
1/2



Decoprint panel




3



4



Decoprint panel



IBIS STYLE HOTEL - PALEXPO - GENÈVE (Switzerland)
Decochoc panel


RETAIL



MIGROS SUPERMARKETS (Switzerland)
Decoprint panel
Designer ONE BY ONE
1/2






CITY MALL (Jordania)
Decoprint thermoformed panel
Amman Decoration House



EDEKA SUPERMARKETS (Germany)
Decoprint & Decochoc panels
1/2/3/4



OFFICES
PUBLIC BUILDING



INDUSTRY
CLEANROOMS



Decoclean thermowelded panel



Decochoc panel



Decoclean thermowelded panel



Decochoc panel



Impact wall protection rail



Decoclean thermowelded panel


TRENDY & DESIGN



EXCELLENT CARE CLINICS (Netherlands)
Decochoc & Decochoc H₂O panels
1/2




MATERNITY WARD HOSPITAL HOROVICE (Czech Republic)
Decochoc & Decoprint panels / Profila corner protector
1/2/3



MAINZ CASINO (Germany)
Cutout Decochoc panel

UNUSUAL




MATERNITY WARD - NORTH WEST HOSPITAL - VILLEFRANCHE SUR SAÔNE (France)
Decoprint panel
Graphist: Benjamin Fessetaud
1/2/3




REDCLIFE QUEENSLAND HOSPITAL (Australia)
Decoprint panel



HAUT LÉVÊQUE HOSPITAL - PESSAC (France)
Decochoc panel with inlaid signage / Linea Touch handrail
1/2/3/4/5



IKAZIA HOSPITAL (Netherlands)
Decoprint panel



COLOUR AVAILABILITY SUMMARY CHART

		WALL PROTECTION																																																				
		0001 Chalk	0031 Alum	0032 Flint	0033 Slate	0034 Basalt	0011 Pebble	0002 Gravel	0003 Clay	0004 Granite	0014 Cinnamon	0009 Sienna	0010 Bark	0005 Schist	0006 Ivory	0007 Wicker	0008 Sand	0013 Greige	0021 Straw	0022 Apricot	0027 Melon	0028 Poppy	0034 Magnolia	0015 Lavender grey	0030 Iris	0029 Garnet	0016 Glacier	0018 Azure	0017 Bluebell	0020 Denim	0024 Bamboo	0023 Meadow	0025 Emerald	0019 Ultramarine	0060 Maple	0061 Beech	0062 Light oak	0067 Wenge	0065 Stripped pine	0069 Brown cedar	0068 Smoky cedar	0050 Brushed aluminium	0051 Composite	0052 Light concrete	0053 Medium concrete	0080 Silver	0081 Copper	0082 Gold	1102 Spume					
LINEA'PUNCH NEO	p.52	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●																					
IMPACT 200 / 120	p.54	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●																					
IMPACT 60	p.54	●	○	○	○		●	○	○	●	○	○	○	○	●	●	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																					
COMBO'PUNCH 200 / 125	p.56	●	○	○	○		○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																					
COMBO'PUNCH 100D	p.58	●	○	○	○		○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																					
COMBO'BEDKIT	p.59	●	○	○	○		○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																					
CONTACT 350	p.60	●	○	○	○		●	●	●	●	○	●	○	●	●	●	○	○	●	●	●	○		○	○	○	○	○	●	●	●	○	○	○																				
CONTACT 200	p.60	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●																					
COMBO'CLAD 200 / 150	p.62	●	○	○	○		○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																					
DECOCHOC	p.64	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●																						
DECOSMIC	p.66																																																					
DECOWOOD	p.68																																																					
DECOTREND	p.69																																																					
DECOCLEAN	p.70	●					●			●					●	●																																						
DECOCHOC H ₂ O	p.72						●	●	○		●	○					○		○							○	●	○				○																						
DECOWOOD / DECOTREND H ₂ O	p.74																																																					
DECOCHOC STARO	p.76	●	●	●								●			●	●		●									●																											
FIN'COLOR	p.79	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
DECOFRESC <i>all public contemporary</i>	p.80	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
FIN'ANGLE	p.87						●	●	○		●	○					○		○								○	●	○				○																					
CORNER PROTECTION																																																						
CORNEA	p.92	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	
CORNEAFLEX	p.93	●	○	○	○		●	○	○	●	○	○	○	○	●	●	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○
COMBO'CORNER	p.94	●	○	○	○	●	○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	
LINEA'FLEX	p.96	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
PROTECTA 2	p.97	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
COMBO'FLEX	p.98	●							●					●	●																																							
COMBO'LINE	p.99	●	○	○	○		○	○	●	○	○	○	○	●	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○		
PROFILA	p.100	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
DOOR PROTECTION																																																						
FOOT-HEIGHT DOOR Contact 200 plate	p.106	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
FOOT-HEIGHT DOOR Contact 350 plate	p.106	●	○	○	○		●	●	●	●	○	●	○	●	●	●	○	○	●	●	●	○		○	○	○	○	○	●	●	●	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	○	
HALF-HEIGHT STRAIGHT Decochoc / Decosmic panels	p.107	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
HALF-HEIGHT DECORATIVE Decochoc / Decosmic panels	p.108	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
HANDPLATES Decochoc / Decosmic panels	p.110	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
INLAID SIGNAGE Decochoc / Decosmic panels	p.111	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		
EDGES AND FRAMES Decochoc / Decosmic panels	p.112	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	

COLOUR AVAILABILITY SUMMARY CHART

			0001 Chalk	0031 Alum	0032 Flint	0033 Slate	0036 Basalt	0011 Pebble	0002 Gravel	0003 Clay	0004 Granite	0014 Cinnamon	0009 Sienna	0010 Bark	0005 Schist	0006 Ivory	0007 Wicker	0008 Sand	0013 Greige	0021 Straw	0022 Apricot	0027 Melon	0028 Poppy	0034 Magnolia	0015 Lavender grey	0030 Iris	0029 Garnet	0016 Glacier	0018 Azure	0017 Bluebell	0020 Denim	0024 Bamboo	0023 Meadow	0025 Emerald	0019 Ultramarine	0060 Maple	0061 Beech	0062 Light oak	0067 Wenge	0065 Stripped pine	0069 Brown cedar	0068 Smoky cedar	0050 Brushed aluminium	0051 Composite	0052 Light concrete	0053 Medium concrete	0080 Silver	0081 Copper	0082 Gold		
HANDRAILS																																																			
ESCORT'DUO	- HANDRAIL	p. 118	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●																	
	- WALL PROTECTION RAIL		●	○	○	○		○	○	●	○	○	○	○	○	○	●	○	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○																
LINEA'DUO	- HANDRAIL	p. 118	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●																
	- WALL PROTECTION RAIL		●	○	○	○		○	○	●	○	○	○	○	○	○	●	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○	○																
PERFORMER 2		p. 120	●					●	●	●	●	○	●	○	●	●	●	○	○	●	●	●	○		○	○	○	○	○	○	●	●	●	○	○	○															
COMBO'DUO		p. 122	●	○	○	○		○	○	●	○	○	○	○	○	●	●	○	○	○	○	○	○		○	○	○	○	○	○	○	○	○	○	○	○															
STARLINE-PVC SHEATHED		p. 124	●						●																																										
BAND FOR STARLINE	- PVC SHEATHED	p. 124	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●															
	- ANODISED	p. 126	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	
LINEA'TOUCH and LINEA'TOUCH+ PVC SHEATHED		p. 128	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●															
- LED OPTION		p. 130	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●														
LINEA'TOUCH - DECOWOOD		p. 132																																			●	●	●	●	●	●									
- LED OPTION		p. 134																																			●	●	●	●	●	●									
LINEA'TOUCH - ANODISED		p. 132																																																	
- LED OPTION		p. 134																																																	
ESCORT - PVC SHEATHED		p. 136	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●		●	●	●	●	●	●	●	●	●	●	●	●	●														
ESCORT - DECOWOOD		p. 138																																			●	●	●	●	●	●									
ESCORT - ANODISED		p. 138																																																	

- In stock
within the limit of available stocks
- On order
with minimum quantity of 200 mU/m² within 4 to 8 weeks depending on produtcs and colours

		0092 Fawn	0093 Swan	0091 Dolphin	0090 Canary	Yellow
INDIVIDUAL PROTECTION						
SAFY'CORNER	p. 141	●	●	●	●	
SAFY'DOOR	p. 142	●	●	●	●	
SAFY'HAND	p. 143					●

- In stock
within the limit of available stocks

		Black
INDUSTRIAL PROTECTION		
ELASTO'FLEX 100V	p. 145	●
ELASTO'PUNCH 200E	p. 146	●
ELASTO'PUNCH 100D	p. 147	●

- In stock
within the limit of available stocks

DOCUMENTS AND SAMPLE CARDS

AVAILABLE



SPM BROCHURE

You will find in this catalogue, all relevant technical information on our products: cut to scale 1, description, application, colour palette...




SPECIAL ISSUE DECOPRINT

SPM SOLUTIONS


HEALTHCARE



PUBLIC BUILDING



HOUSING



HOTEL



SAMPLE CARD

This tool has been created to help you choose colours in your projects. All colours from the SPM range are presented with movable samples.



47 COLOURS AND DECORS SPM PALETTE




Colours are not contractually binding.

PHOTO BOOK SPM



Healthcare, Education, Industry, Hotels, Sport... SPM presents you photos of different achievements and product applications.



INSTALLATION PROCEDURES



A guide which precisely details installation conditions and steps to follow.

A	
Antibacterial.....	p. 07
B	
Bactericidal.....	p. 07
Bacteriostatic.....	p. 07
Bendings	p. 112/113
Brochures	p. 182/183
C	
Case - Wall welding	p. 152
Colour swatches	p. 38 to 45 & 183
Colours	p. 38 to 45 & 178 to 181
Combo'Bedkit	p. 55
Combo'Clad.....	p. 58
Combo'Corner.....	p. 94/95
Combo'Duo	p. 118
Combo'Flex	p. 94
Combo'Line.....	p. 95
Combo'Punch.....	p. 52 to 54
Contact 350/200	p. 60/61 & 106
Contents.....	p. 03
Cornea.....	p. 92
Corneaflex.....	p. 93
Curving	p. 150
Cutter - Hooked blade	p. 152
D	
Decocare	p. 84
Decochoc.....	p. 64/65
Decochoc H ₂ O.....	p. 72/73
Decoclean.....	p. 70/71
Decofresc	p. 44 & 80/81
Decokid	p. 44 & 85
Decoprint.....	p. 82/83
Decosmic.....	p. 43 & 66/67
Decotrend.....	p. 42 & 69
Decotrend H ₂ O.....	p. 74/75
Decowood.....	p. 40/41 & 68
Decowood H ₂ O.....	p. 74/75
E	
Early Childhood.....	p. 44 & 81
Edges	p. 108
Elasto'Flex.....	p. 145
Elasto'Punch	p. 146/147
Escort-Anodised	p. 138/139
Escort-Decowood.....	p. 138/139
Escort'Duo	p. 118/119
Escort-PVC sheathed.....	p. 136/137
Environment.....	p. 12/13
F	
Fin'Alu	p. 78
Fin'Angle	p. 87
Fin'Color.....	p. 79
Fixing and finishing.....	p. 87 & 149
Food contact.....	p. 09
Frames	p. 112/113
Fire rating	p. 11
H	
Handplates	p. 110
Hygiene	p. 07 & 08/09
I	
Impact 200/120/60	p. 54/55
Impacts	p. 11

Inlaid signage.....	p. 107
Innovation.....	p. 14/15
ISO 5	p. 09 & 70/71
L	
Linea'Duo	p. 118/119
Linea'Flex.....	p. 96
Linea'Punch Neo.....	p. 52/53
Linea'Touch:	
- Anodised	p. 132/133
- Decowood.....	p. 132/133
- PVC sheathed.....	p. 128/129
Linea'Touch LED:	
- Anodised	p. 134/135
- Decowood.....	p. 134/135
- PVC sheathed.....	p. 130/131
M	
Masks for doors	p. 108 to 110
N	
Nuclear decontamination	p. 09
Numbers	p. 111
P	
Palette of colours.....	p. 38/39
Performer 2	p. 120/121
Photo book	p. 154/177
Pictos	p. 111
Plac'Inox.....	p. 86
Profila 50 & 30	p. 100
Protecta 2.....	p. 97
Profil'Inox 50 & 30.....	p. 101
R	
Rapid'Access®	p. 150
Rapid'Angle®	p. 151
Resistance.....	p. 09 & 11
Roller (smoothing).....	p. 153
S	
Safy'Corner	p. 141
Safy'Door.....	p. 142
Safy'Hand	p. 143
Scratches	p. 11
Service ducts.....	p. 150
Signage inlaid	p. 111
Smoothing Roller	p. 153
Solutions	
- corner protection	p. 88/91
- door protection	p. 102/104
- for handrails	p. 150/151
- for panels.....	p. 79 & 148/149
- handrails.....	p. 114/117
- per sector	p. 16/37
- wall protection.....	p. 48/51
Stains	p. 11
Starline-Anodised	p. 126/127
Starline-PVC sheathed	p. 124/125
T	
Thermal expansion	p. 153
Thermoforming.....	p. 113 & 149
Thermowelding.....	p. 148
Tools	p. 152/153
V	
Virucidal	p. 07



spm-international.com

PANELS HANDRAILS PROTECTION RAILS CORNER PROTECTION

ASIA: Gerflor Asia

Tel: +86 21 6357 8818 - Fax: +86 21 6357 8998

e-mail: gerflorasia@gerflor.com

AUSTRALIA/NEW ZEALAND: Gerflor Australasia Pty. Ltd

Australia Tel: 1 800 060 785 - New Zealand Tel: 0 800 630 119

e-mail: gerflor@gerflor.com.au

AUSTRIA/SWITZERLAND: Webamed-Spm GmbH

Tel: +49 2351 954550 - Fax: +49 2351 954580

e-mail: info@webamed-spm.de - webamed-spm.de

BELGIUM/LUXEMBURG: Gerflor Benelux

Tel: +32 (0)3 766 42 82 - Fax: +32 (0)3 766 29 14

e-mail: gerflorbel@gerflor.com

CANADA: Gerflor International

Tel: +1 438 333 0752 - Fax: +1 438 380 5425

e-mail: gerflorcanada@gerflor.com

CHINA: Gerflor floorings (China) Co. Ltd.

Tel: +86 21 6357 8818 - Fax: +86 21 6357 8998

e-mail: gerflorchina@gerflor.com

FINLAND: Gerflor Oy

Tel: +358 (0) 10 6 17 5150 - Fax: +358 (0) 10 617 5152

e-mail: info@gerflor.fi

FRANCE: SPM International

Tel: + 33 (0)5 34 39 41 00 - Fax: +33 (0)5 34 39 40 10

e-mail: export@spm.fr

GERMANY: Webamed-Spm GmbH

Tel: +49 2351 954550 - Fax: +49 2351 954580

e-mail: info@webamed-spm.de - webamed-spm.de

ITALY: Gerflor S.p.A.

Tel: +39 02 90 40 10 - Fax: +39 02 90 42 74 84

e-mail: gerfloritalia@gerflor.com

LATIN AMERICA (Brazil): Gerflor América Latina

Tel: +55 11 38 48 20 20

e-mail: gerflor@gerflor.com.br

MIDDLE EAST: Gerflor Middle East

Tel: +966 13 847 1779 - Fax: +966 13 847 1781

e-mail: info@gerflorme.com

NETHERLANDS: Gerflor Benelux

Tel: +31 (0)40 266 17 00 - Fax: +31 (0)40 257 46 89

e-mail: gerflornl@gerflor.com

OTHER COUNTRIES: SPM International

Tel: + 33 (0)5 34 39 41 00 - Fax: +33 (0)5 34 39 40 10

e-mail: export@spm.fr

POLAND: Gerflor Polska Sp z o.o

Tel: + 48 61 823 34 01 - Fax: + 48 61 823 34 33

e-mail: info@gerflor.pl

PORTUGAL: Gerflor Iberia, SA

Tel: +351 21 843 95 49 - Fax: +351 21 846 55 44

e-mail: gerflorportugal@gerflor.com

RUSSIA: Gerflor zao

Tel./Fax: + 7 495 785 23 71

e-mail: gerflorrussia@gerflor.ru

SCANDINAVIA: Gerflor Scandinavia a.s.

Tel: + 47 64 95 60 70 - Fax: + 47 64 95 60 80

e-mail: gerflorscand@gerflor.no

SPAIN: Gerflor Iberia, SA

Tel: +34 91 653 50 11 - Fax: +34 91 653 25 85

e-mail: gerfloriberia@gerflor.com

USA: Gerflor North America

Tel: 877 GERFLOR (437 3567) - Fax: 847 394 3753

e-mail: info@gerflorusa.com



Committed to sustainable development

A company of **Gerflor**

Spm[®]
wall protection